
DEFINITE PROJECT REPORT/ENVIRONMENTAL ASSESSMENT

AROOSTOOK, FORT FAIRFIELD, MAINE

MAIN REPORT / SUPPORTING DOCUMENTATION

LOCAL FLOOD PROTECTION

DRAFT REVIEW

AUGUST 1987



**US Army Corps
of Engineers**
New England Division

AROOSTOOK RIVER
FLOOD DAMAGE REDUCTION PROJECT
FT. FAIRFIELD, MAINE

TECHNICAL APPENDICIES
FOR
DEFINITE PROJECT REPORT
FOR
WATER RESOURCES DEVELOPMENT

DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION CORPS OF ENGINEERS
WALTHAM, MASSACHUSETTS 02254-9194

AUGUST 1987

TABLE OF CONTENTS

SECTION

- | | |
|----------|---|
| A | Hydrologic Analysis |
| B | Geotechnical and Design Considerations |
| C | Structural Design |
| D | Social and Economic Analysis |
| E | Real Estate |

SECTION A

HYDROLOGIC ANALYSIS

AROOSTOOK RIVER FLOOD CONTROL
FORT FAIRFIELD, MAINE

HYDROLOGIC ANALYSIS
FOR
DETAILED PROJECT REPORT

by

HYDROLOGIC ENGINEERING SECTION
WATER CONTROL BRANCH
ENGINEERING DIVISION

NEW ENGLAND DIVISION, CORPS OF ENGINEERS
WALTHAM, MASSACHUSETTS

AROOSTOOK RIVER FLOOD CONTROL
FORT FAIRFIELD, MAINE

TABLE OF CONTENTS

| <u>Paragraph</u> | <u>Subject</u> | <u>Page</u> |
|------------------|--|-------------|
| 1. | PURPOSE | 1 |
| 2. | WATERSHED DESCRIPTION | 1 |
| 3. | CLIMATOLOGY | 1 |
| | a. General | 1 |
| | b. Temperature | 2 |
| | c. Precipitation | 2 |
| | d. Snowfall | 2 |
| 4. | STREAMFLOW | 4 |
| | a. General | 4 |
| | b. Streamflow Records | 4 |
| 5. | FLOOD HISTORY | 5 |
| | a. General | 5 |
| | b. April 1973 | 7 |
| | c. December 1973 | 7 |
| | d. May 1974 | 7 |
| | e. April 1976 | 7 |
| | f. April 1983 | 7 |
| | g. Ice Jams | 8 |
| 6. | FLOOD FREQUENCIES | 8 |
| 7. | ANALYSIS OF FLOODS | 10 |
| | a. General | 10 |
| | b. Flood Profiles | 10 |
| | c. Stage Discharge Relations | 10 |
| | d. Stage Frequency Relations | 11 |
| 8. | STANDARD PROJECT FLOOD | 12 |
| | a. General | 12 |
| | b. Standard Project Rainfall and Snowmelt | 12 |
| | c. Unit Hydrograph | 13 |
| | d. Standard Project Flood | 14 |
| 9. | FLOOD CONTROL IMPROVEMENTS | 14 |
| | a. General | 14 |
| | b. Project Design Flood | 14 |
| | c. Level of Protection | 15 |
| | d. Riprap Design | 15 |
| | e. Alternative Levels of Protection | 15 |
| | (1) Two Percent Chance Design | 15 |
| | (2) Standard Project Flood Design | 16 |
| | f. Interior Drainage | 16 |
| | (1) General | 16 |
| | (2) High Level Watershed | 16 |
| | (3) Low Level Watershed | 16 |

LIST OF TABLES

| <u>Table</u> | <u>Title</u> | <u>Page</u> |
|--------------|--|-------------|
| 1 | Monthly Temperature - Caribou and Presque Isle, Maine | 2 |
| 2 | Monthly Precipitation - Caribou and Fort Fairfield, Maine | 3 |
| 3 | Monthly Snowfall - Caribou and Fort Fairfield, Maine | 4 |
| 4 | Monthly Runoff - Aroostook River at Washburn, Maine | 5 |
| 5 | Annual Peak Discharges - Aroostook River at Washburn, Maine | 6 |
| 6 | Annual Peak Stages - Aroostook River at Washburn, Maine | 9 |
| 7 | Historic Ice James - Aroostook River at Fort Fairfield, Maine | 11 |
| 8 | Spring Season Standard Project Flood Runoff at Fort Fairfield | 13 |
| 9 | Aroostook River - Pertinent Unit Hydrograph Data | 14 |

LIST OF PLATES

| <u>Plate No.</u> | <u>Title</u> |
|------------------|---|
| 1 | Aroostook River Watershed Map |
| 2 | Discharge Frequency Curves - Aroostook River at Washburn and Fort Fairfield |
| 3 | Discharge Rating Curves - Aroostook River at Limestone Road Bridge |
| 4 | Stage Frequency Curves - Aroostook River at Limestone Road Bridge |
| 5 | Unit Hydrograph Analysis - April 1973 Flood |
| 6 | Standard Project Flood |
| 7 | Plan and Profile - Aroostook River at Fort Fairfield |

AROOSTOOK RIVER FLOOD CONTROL
FORT FAIRFIELD, MAINE

HYDROLOGIC ANALYSIS

1. PURPOSE

This report presents hydrologic information and analysis pertinent to the planning and design of flood control improvements along the Aroostook River within the town of Fort Fairfield, Maine. Included are sections on watershed description, climatology, flood frequencies, analysis of floods, and improvements for flood control.

2. WATERSHED DESCRIPTION

The Aroostook River is a tributary of the Saint John River in northern Maine and western New Brunswick, Canada. Its watershed is situated between those of the Penobscot and Allagash Rivers to the west; the Fish River to the north; the Saint John to the east, and the Meduxnekeag River to the south. The Aroostook River originates at the junction of the Munsungan and Millinocket streams in the northwest corner of Penobscot County, Maine and flows in a general northeasterly direction for about 100 miles through Aroostook County before crossing the international boundary below Fort Fairfield. After crossing the international boundary, the Aroostook River flows an additional five miles in an easterly direction through New Brunswick, Canada to its confluence with the Saint John River at Aroostook Junction, Canada. Of the total drainage area of 2,418 square miles, approximately 2,300 square miles lie upstream of Fort Fairfield, which is essentially the entire portion of the basin within Maine. A hydroelectric project, Tinker Dam, with a drainage area of 2,370 square miles and a head of 85 feet, is located 2 miles downstream of the international boundary. The Aroostook is a flat, heavily forested, hydrologically sluggish watershed having a total fall of about 450 feet in its 107 mile watercourse to the Saint John River. However, 85 feet or about 19 percent of the total fall is at Tinker Dam with the remaining 365 feet occurring as a rather uniform slope over the 105 mile river course above Tinker Dam. A map of the Aroostook River watershed is shown on Plate 1.

3. CLIMATOLOGY

a. General. The climate of the Aroostook River basin is cold and semi-humid with an average temperature of about 40° Fahrenheit and yearly precipitation of approximately 37 inches. Due to its northerly location, the area has escaped the brunt of coastal hurricanes with their accompanying intense rainfall. The area does experience periods of moderate rain and/or snowfall as a result of low pressure systems moving up the east coast and from frontal systems moving from west to east across the country.

b. Temperature. Average monthly temperatures in the basin vary considerably throughout the year. Summers are cool with temperatures averaging 60 to 65° Fahrenheit with only occasional rises into the nineties. Winters are long and cold with temperatures averaging 10 to 20° Fahrenheit. The mean, maximum and minimum monthly temperatures at two stations in the Aroostook River watershed, as published by the National Oceanic and Atmospheric Administration (NOAA), are summarized in Table 1.

TABLE 1

MONTHLY TEMPERATURE
(Degree Fahrenheit)

| Month | Caribou, Maine 46 Year Record Elevation 624 FEET/NGVD | | | Presque Isle, Maine 70 Year Record Elevation 599 FEET/NGVD | | |
|-----------|---|------|------|--|------|------|
| | Mean | Max | Min | Mean | Max | Min |
| January | 10.0 | 51 | -32 | 11.5 | 54 | -41 |
| February | 13.1 | 47 | -41 | 13.4 | 51 | -37 |
| March | 23.9 | 58 | -20 | 24.8 | 65 | -30 |
| April | 36.9 | 80 | 2 | 38.0 | 85 | -2 |
| May | 50.3 | 91 | 19 | 51.2 | 94 | 19 |
| June | 59.9 | 96 | 30 | 60.7 | 95 | 25 |
| July | 65.2 | 95 | 40 | 66.1 | 97 | 37 |
| August | 62.7 | 95 | 34 | 63.8 | 99 | 31 |
| September | 53.9 | 91 | 23 | 55.1 | 90 | 21 |
| October | 43.2 | 79 | 14 | 44.4 | 84 | 8 |
| November | 31.0 | 68 | -2 | 31.6 | 69 | -15 |
| December | 15.3 | 58 | -24 | 16.7 | 58 | -35 |
| Annual | 38.8 | 41.8 | 36.2 | 39.8 | 50.7 | 29.6 |

c. Precipitation. The average annual precipitation over the Aroostook River watershed is about 37 inches and is distributed rather uniformly throughout the year with slightly greater amounts during the summer months. Periods of moderate rainfall are usually not more than 1 to 2 days in duration and storm rainfall amounts generally do not exceed 1 to 2 inches. Monthly and annual precipitation for two locations within the Aroostook River watershed are shown in Table 2.

d. Snowfall. Practically all winter precipitation occurs as snow with the total fall averaging about 100 inches per year. Snow survey data for the watershed is limited but based on information gathered in adjacent



basins the snowpack generally reaches a maximum in April. Average water equivalent of the spring snowpack is about 8 inches with maximums as high as 15 inches. Table 3 lists the mean, monthly and annual snowfall for two locations in the watershed.

TABLE 2

MONTHLY PRECIPITATION
(Inches)

| <u>Month</u> | Caribou, Maine 46 Year Record <u>Elevation 624 FEET/NGVD</u> | | | Fort Fairfield, Maine 48 Year Record <u>Elevation 300 FEET/NGVD</u> | | |
|--------------|--|------------|------------|---|------------|------------|
| | <u>Mean</u> | <u>Max</u> | <u>Min</u> | <u>Mean</u> | <u>Max</u> | <u>Min</u> |
| January | 2.23 | 5.10 | 0.12 | 2.64 | 5.52 | 0.38 |
| February | 2.11 | 4.13 | 0.26 | 2.40 | 5.38 | 0.19 |
| March | 2.50 | 5.13 | 0.66 | 2.60 | 5.82 | 0.52 |
| April | 2.59 | 5.26 | 0.54 | 2.80 | 5.15 | 0.85 |
| May | 30.3 | 6.27 | 0.47 | 3.13 | 6.87 | 0.94 |
| June | 3.47 | 7.11 | 0.88 | 3.69 | 7.62 | 1.41 |
| July | 4.06 | 6.83 | 1.75 | 4.26 | 7.44 | 1.62 |
| August | 3.94 | 12.09 | 0.93 | 3.64 | 7.90 | 1.23 |
| September | 3.27 | 8.14 | 0.86 | 3.78 | 7.75 | 0.79 |
| October | 3.17 | 6.35 | 0.63 | 3.52 | 7.65 | 0.98 |
| November | 3.40 | 8.15 | 0.45 | 3.47 | 7.36 | 0.39 |
| December | 3.00 | 7.97 | 0.74 | 3.25 | 7.40 | 0.82 |
| Annual | 36.77 | 51.10 | 27.92 | 39.18 | 55.27 | 27.95 |

TABLE 3

MONTHLY SNOWFALL
(Inches)

| Caribou, Maine 39 Year Record Elevation 624 FEET/NGVD | | | | Fort Fairfield, Maine 19 Year Record Elevation 300 FEET/NGVD | | |
|---|-------------|------------|------------|--|------------|------------|
| <u>Month</u> | <u>Mean</u> | <u>Max</u> | <u>Min</u> | <u>Mean</u> | <u>Max</u> | <u>Min</u> |
| January | 23.3 | 41.4 | 2.2 | 22.8 | 40.1 | 3.6 |
| February | 22.2 | 41.0 | 4.4 | 17.4 | 37.5 | 4.0 |
| March | 19.7 | 47.1 | 6.1 | 19.7 | 45.5 | 4.0 |
| April | 8.3 | 24.4 | T | 5.9 | 17.0 | 1.0 |
| May | 0.8 | 10.9 | 0 | 0.3 | 4.0 | 0 |
| June | 0 | T | 0 | 0 | T | 0 |
| July | 0 | 0 | 0 | 0 | 0 | 0 |
| August | 0 | 0 | 0 | 0 | 0 | 0 |
| September | 0 | T | 0 | 0 | 0 | 0 |
| October | 2.1 | 12.1 | 0 | 1.4 | 10.0 | 0 |
| November | 12.1 | 34.9 | 1.5 | 7.5 | 24.0 | 1.0 |
| December | 23.8 | 59.9 | 6.5 | 25.1 | 41.0 | 3.6 |
| Annual | 112.3 | 181.1 | 59.6 | 94.9 | 141.6 | 58.9 |

4. STREAMFLOW

a. General. Average streamflow in the Aroostook basin is about 1.6 cfs per square mile of drainage area, which is equivalent to about 22 inches of runoff per year or about 60 percent of average annual precipitation. Streamflow, however, is quite variable seasonally. Much of the winter precipitation occurs as snow, which does not run off but accumulates as deep snowpack. As a result, over 50 percent of the annual runoff occurs during the April-May spring snowmelt period. Maximum streamflow rates on the Aroostook River have been as high as 26 cfs per square mile of drainage area and lows frequently approach 0.1 cfs per square mile, generally occurring in late summer or the dead of winter.

b. Streamflow Records. There are no long term streamflow records for the Aroostook River in Fort Fairfield, Maine. There is, however, a long term USGS gaging station on the main stem Aroostook River located upstream of Fort Fairfield in the town of Washburn, Maine. This gage, with a drainage area of 1,654 square miles or 68 percent of the total Aroostook River watershed, has continuously recorded discharges since 1931. The discharge record at this station was used extensively in analyzing the hydrologic characteristics of the Aroostook River in Fort

Fairfield. Table 4 lists average monthly runoff as recorded at the Washburn gage. Average monthly runoff varies from about 6 inches in May to 0.6 inch in August and February. Extremes in monthly runoff have ranged from a high of over 14 inches in May to a low of 0.06 inch in February. In addition, annual peak flows at the gage are listed in Table 5.

TABLE 4
MONTHLY RUNOFF
AROOSTOOK RIVER AT WASHBURN, MAINE
D.A = 1,654 SQUARE MILES
(Continuous Recording Period 1931-1983)

| Month | Mean | | Maximum | | Minimum | |
|-----------|------|--------|---------|--------|---------|--------|
| | cfs | Inches | cfs | Inches | cfs | Inches |
| January | 1010 | 0.70 | 2595 | 1.81 | 167 | 0.12 |
| February | 1000 | 0.63 | 3684 | 2.32 | 101 | 0.06 |
| March | 1432 | 1.00 | 10440 | 7.28 | 324 | 0.23 |
| April | 7693 | 5.19 | 16990 | 11.46 | 1468 | 0.99 |
| May | 8518 | 5.94 | 20350 | 14.18 | 3229 | 2.25 |
| June | 2556 | 1.72 | 5931 | 4.00 | 658 | 0.44 |
| July | 1402 | 0.98 | 5882 | 4.10 | 261 | 0.18 |
| August | 1042 | 0.73 | 5728 | 3.99 | 152 | 0.11 |
| September | 1169 | 0.79 | 5235 | 3.53 | 144 | 0.10 |
| October | 1752 | 1.22 | 8098 | 5.64 | 265 | 0.18 |
| November | 2501 | 1.69 | 9767 | 6.59 | 218 | 0.15 |
| December | 1848 | 1.29 | 7975 | 5.56 | 175 | 0.12 |
| Annual | 2666 | 21.88 | 4145 | 34.02 | 1409 | 11.56 |

5. FLOOD HISTORY

a. General. Floods along the Aroostook River have occurred to varying degrees over the years resulting from intense rainfall, snowmelt or ice jams, or from combinations of the three. The main flood season on the Aroostook River occurs in the spring when the chance of significant rainfall, and/or high temperatures, during the spring snowmelt period, pose an annual flood threat. As indicated by the listing of annual peak flows in Table 5, about 90 percent of the annual high flows occur during the spring months of March through May. In addition, ice jams are a major flood hazard every spring as well as being a major threat to bridge crossings and other structures.

The largest recorded discharge at Washburn was 43,400 cfs and occurred in April 1983. This flow was slightly greater in magnitude than the previous discharge of record of 43,100 cfs that occurred in April 1973. Available records indicated significant ice jam flood events occurred in the Fort Fairfield area in April 1976, March 1936, April 1940,

TABLE 5

ANNUAL PEAK DISCHARGES
AROOSTOOK RIVER AT WASHBURN, MAINE
(Drainage Area = 1,654 Square Miles)

| <u>Date</u> | <u>Discharge</u> (cfs) | <u>Date</u> | <u>Discharge</u> (cfs) |
|-------------|---------------------------|-------------|---------------------------|
| 13 Apr 1931 | 13,500 | 16 May 1960 | 25,000 |
| 13 Apr 1932 | 20,900 | 16 May 1961 | 37,000 |
| 4 May 1933 | 24,000 | 17 Jul 1962 | 19,200 |
| 21 Apr 1934 | 36,200 | 3 May 1963 | 23,000 |
| | | 10 Nov 1963 | 29,200 |
| 1 May 1935 | 23,300 | | |
| 22 Mar 1936 | 37,800 | 2 May 1965 | 7,670 |
| 30 Apr 1937 | 15,500 | 26 Apr 1966 | 14,500 |
| 22 Apr 1938 | 17,500 | 5 May 1967 | 18,400 |
| 11 May 1939 | 30,100 | 16 Apr 1968 | 17,800 |
| | | 11 May 1969 | 27,600 |
| 14 Apr 1940 | 30,900 | | |
| 22 Apr 1941 | 27,100 | 26 Apr 1970 | 25,600 |
| 28 Apr 1942 | 26,000 | 5 May 1971 | 28,000 |
| 13 May 1943 | 24,400 | 17 May 1972 | 24,200 |
| 11 Nov 1943 | 16,300 | 30 Apr 1973 | 43,100 |
| | | 1 May 1974 | 42,800 |
| 3 Apr 1945 | 21,000 | | |
| 28 Apr 1946 | 22,900 | 8 May 1975 | 20,200 |
| 8 May 1947 | 31,800 | 4 Apr 1976 | 32,200 |
| 20 May 1948 | 14,200 | 25 Apr 1977 | 27,200 |
| 18 Apr 1949 | 14,000 | 30 Apr 1978 | 19,200 |
| | | 30 Apr 1979 | 37,700 |
| 23 Apr 1950 | 22,100 | | |
| 30 Nov 1950 | 23,000 | 16 Apr 1980 | 13,400 |
| 30 Apr 1952 | 18,700 | 18 Aug 1981 | 17,200 |
| 3 Apr 1953 | 32,600 | 28 Apr 1982 | 31,500 |
| 29 Jun 1954 | 32,400 | 19 Apr 1983 | 43,400 |
| | | 2 Jun 1984 | 25,500 |
| 6 May 1955 | 20,200 | | |
| 16 May 1956 | 12,500 | | |
| 24 Apr 1957 | 13,500 | | |
| 25 Apr 1958 | 35,400 | | |
| 27 Apr 1959 | 13,600 | | |

and December 1973. Following are discussions of five of the more notable floods that have occurred within Fort Fairfield over the past 20 years. Flows at Fort Fairfield are generally proportioned to those at Washburn by a ratio of drainage area.

b. April 1973. Between 22 and 30 April 1973, 3.06 inches of precipitation combined with daytime temperatures in the sixties produced high discharges on the Aroostook River. The peak discharge recorded on the 30th at the USGS gage in Washburn was 43,100 cfs, the second largest flow in the 53 year period of record, and the Maine Public Service Company reported a flow of 60,800 cfs at Tinker Dam. Ice flows on the river during this flood contributed to flood damages but peak flood levels were due to the abnormally high river flows unaffected by any jams. The estimated peak flow at Fort Fairfield was 58,100 cfs.

c. December 1973. On Thursday, 20 December, over 3 inches of snow and about 0.3 inches of rain fell with temperatures below freezing. On Friday, temperatures warmed to near 50° Fahrenheit and an additional 0.85 inches of rain fell resulting in a one-half mile long ice jam in the Fort Fairfield area with flooding to about 7 feet above normal river levels. This flood was principally an ice jam event with a maximum discharge, at the Washburn gage, of only about 14,000 cfs.

d. May 1974. During the period 28 April to 1 May, 1.35 inches of rain fell in the Aroostook basin and with daytime temperatures in the sixties, the third highest flow of record (42,800 cfs on 1 May) was experienced on the Aroostook River at Washburn, occurring only one year following the flood of April 1973. Though ice flows occurred during this event, the resulting flood was due mostly to the abnormally high river flows. The estimated peak flow at Fort Fairfield was 57,700 cfs.

e. April 1976. Probably the most devastating flood on the Aroostook River in the Fort Fairfield area occurred during the period 3-6 April 1976 and was the result of high flows with extensive ice jams comprised of ice chunks up to 43 inches in thickness. The peak discharge at the Washburn gage was 32,200 cfs with the stage surcharged about 3.7 feet by ice jams. At Fort Fairfield, the peak discharge was estimated to be 43,400 cfs with stage surcharged about 5 feet by a massive ice jam resulting in the record flood stage at Fort Fairfield of 365.6 feet NGVD. The April 1976 event was the result of about 1.6 inches of rainfall on 2 through 4 April in combination with daytime temperatures in the forties.

f. April 1983. The April 1983 flood was the result of about 1.6 inches of rainfall occurring between the 16th and 19th of April, preceded by a period of above normal temperatures plus snowmelt, thereby providing high antecedent runoff conditions. The resulting peak discharge recorded on the 19th at the USGS gage at Washburn was 43,400 cfs, the largest flow in the 53 year period of record. The estimated peak flow at Fort Fairfield was 58,500 cfs.

g. Ice Jams. Ice jams are practically an annual event in the Aroostook basin occurring during spring ice-out or at other times during the winter when freshets and temperatures are sufficient to cause river sheet ice breakup. Most frequently ice jams occur during rising riverflows and are broken up by time of peak discharge. The surcharge in river level caused by ice jams can be appreciable. Frequently, peak annual river levels are a result of ice jams occurring at times other than peak discharge. An analysis of peak annual stages and discharges at the Washburn USGS gage indicated that in 22 years out of 53, or 42% of the years, peak annual river levels were the result of ice jams. There obviously were many ice jam occurrences other than those producing peak stage for the year.

Peak annual stages, at the Washburn gage for the period 1931-1983, with those caused by ice jams noted, are listed in Table 6.

Ice jams on the Aroostook River at Fort Fairfield have added significantly to the flood problems of that community. The record flood stage at Fort Fairfield occurred in April 1976 as a result of an ice jam event during a high flow period. The resulting flood levels were about 3 feet higher than those produced by the non-ice jam flood of April 1973.

6. FLOOD FREQUENCIES


Peak discharge frequencies for the Aroostook River were developed by statistical analysis of long term peak flow records in the region. Discharge frequencies were developed for the Aroostook River, at the USGS gage in Washburn, Maine, by statistical analysis using a Log Pearson type III distribution in accordance with guidelines set forth in U.S. Water Resources Council Bulletin 17B, "Guidelines for Determining Floodflow Frequency," revised September 1982. The distribution of peak flows at the Washburn gage, with a drainage area of 1,654 square miles and a period of record of 53 years, had a mean log of 4.3649, a standard deviation of 0.1527, and a computed negative skew 0.40; however, a skew of 0.0 was adopted based on regional studies and broader data bases afforded by such analyses. Discharge frequencies at Fort Fairfield (D.A = 2,230 square miles) were considered proportional to those at Washburn by ratio of respective drainage areas. Other miscellaneous discharge data were also considered in arriving at the adopted frequency relation for the Aroostook River at Fort Fairfield. These data included 7 years of record (1904-1910) at a USGS gage at Fort Fairfield. The adopted discharge frequency curves with expected probability adjustment at Washburn and Fort Fairfield are shown on Plate 2.

TABLE 6

AROOSTOOK RIVER
PEAK ANNUAL STAGES
WASHBURN USGS GAGE
 (1931-1984)

| <u>Date</u> | <u>Stage</u> (ft) | <u>Elevation</u> (ft, NGVD) | <u>Comment</u> |
|-------------|----------------------|--------------------------------|----------------|
| 13 Apr 1931 | 8.00 | 444.4 | |
| 13 Apr 1932 | 9.40 | 445.8 | |
| 4 May 1933 | 9.89 | 446.3 | |
| 21 Apr 1934 | 11.65 | 448.0 | |
| 20 Apr 1935 | 10.69 | 447.1 | Ice Jam |
| 22 Mar 1936 | 11.80 | 448.2 | |
| 30 Apr 1937 | 8.37 | 444.8 | |
| 21 Apr 1938 | 8.60 | 445.0 | |
| 11 May 1939 | 10.00 | 446.4 | |
| 15 Apr 1940 | 13.50 | 449.9 | Ice Jam |
| 17 Apr 1941 | 10.53 | 446.9 | Ice Jam |
| 28 Apr 1942 | 8.84 | 445.2 | |
| 13 May 1943 | 8.47 | 444.9 | |
| 11 Nov 1943 | 6.70 | 443.1 | |
| 3 Apr 1945 | 7.78 | 448.2 | |
| 30 Apr 1946 | 10.00 | 446.4 | Ice Jam |
| 8 May 1947 | 9.58 | 446.0 | |
| 20 May 1948 | 6.05 | 442.4 | |
| 9 Apr 1949 | 9.34 | 445.7 | Ice Jam |
| 23 Apr 1950 | 10.03 | 446.4 | |
| 6 Apr 1951 | 15.78 | 452.2 | Ice Jam |
| 20 Apr 1952 | 10.51 | 446.9 | Ice Jam |
| 30 Mar 1953 | 13.95 | 450.3 | Ice Jam |
| 29 Jun 1954 | 11.84 | 448.2 | |
| 22 Dec 1954 | 13.40 | 449.8 | Ice Jam |
| 18 Apr 1956 | 8.03 | 444.4 | Ice Jam |
| 24 Apr 1957 | 7.72 | 444.1 | |
| 21 Dec 1957 | 14.90 | 451.3 | Ice Jam |
| 11 Apr 1959 | 11.46 | 447.9 | Ice Jam |
| 16 May 1960 | 10.40 | 446.8 | |
| 16 May 1961 | 12.67 | 449.1 | |
| 17 Jul 1962 | 9.20 | 445.6 | |
| 3 May 1963 | 10.00 | 446.4 | |
| 10 Nov 1963 | 11.23 | 447.6 | |
| 2 Dec 1964 | 9.04 | 445.4 | Ice Jam |
| 26 Apr 1966 | 8.00 | 444.4 | |
| 5 May 1967 | 9.00 | 445.4 | |
| 13 Apr 1968 | 10.17 | 446.6 | Ice Jam |
| 11 May 1969 | 10.91 | 447.3 | |
| 26 Apr 1970 | 10.52 | 446.9 | |
| 24 Apr 1971 | 11.23 | 447.6 | Ice Jam |
| 17 May 1972 | 10.24 | 446.6 | |
| 30 Apr 1973 | 13.68 | 450.1 | |
| 24 Dec 1973 | 20.91 | 457.3 | Ice Jam |
| 22 Apr 1975 | 9.46 | 445.9 | Ice Jam |
| 3 Apr 1976 | 14.74 | 451.1 | Ice Jam |
| 3 Apr 1977 | 10.85 | 447.2 | |
| 22 Apr 1978 | 11.93 | 448.3 | Ice Jam |
| 30 Apr 1979 | 13.17 | 449.6 | |
| 11 Apr 1980 | 8.65 | 445.1 | Ice Jam |
| 6 Apr 1981 | 11.17 | 447.6 | Ice Jam |
| 22 Apr 1982 | 15.67 | 452.07 | Ice Jam |
| 19 Apr 1983 | 13.73 | 450.13 | |
| 17 Apr 1984 | 13.46 | 449.86 | Ice Jam |

PEAK DISCHARGE IN 1000 C.F.S.



SAINT JOHN RIVER BASIN
AROOSTOOK RIVER
DISCHARGE FREQUENCY
CURVES
FORT FAIRFIELD MAINE


7. ANALYSIS OF FLOODS

a. General. The large drainage area of the Aroostook River at Fort Fairfield (2,230 square miles) is a hydrologically "sluggish" basin affecting peak discharges and duration of flooding at Fort Fairfield. Because of the large size of the watershed and its character, several days may pass before effects of heavy rains cause peak flows in the study reach. In the same manner, severe flood conditions may persist for as much as a week while reservoirs, lakes and large tracts of land in the southwestern Aroostook basin drain to normal levels.

b. Flood Profiles. Backwater flood profiles on the Aroostook River in Fort Fairfield were computed starting at the United States-Canadian border at river station 231+26 and proceeding upstream a distance of about 4 miles to river station 460+00 (about 1 mile above Limestone Road bridge). The starting water surface elevations for the Aroostook River were determined by developing a discharge rating curve at Tinker Dam, Canada located about 1 mile below the U.S.-Canada border. Information pertinent to the development of the rating curve was furnished by the Maine Public Service Company, Presque Isle, Maine. Tinker Dam is viewed more as a diversion than a high dam facility whereby the power potential of a natural falls is harnessed. The dam is equipped with a main spillway about 270 feet long with a 10 foot high bottom hinged gate. The invert of the gate is elevation 342 feet NGVD and normal maximum pool (gate raised) is elevation 352 feet NGVD. Flood stage discharge ratings were developed assuming the gate fully lowered and a main spillway weir coefficient of 3.6 with flow occurring over concrete non-overflow sections.

Backwater computations were made using cross section data as well as 5 foot contour mapping used in an earlier Aroostook River flood plain information report completed by NED in 1978. Computations were made using the Corps' HEC-2 computer program with Manning's "n" roughness coefficients of 0.03 for channel and 0.07 for overbank areas. Expansion and contraction coefficients were generally 0.3 and 0.1, respectively. The backwater model was calibrated by comparing developed discharge ratings at the Limestone Road bridge in Fort Fairfield with historic highwater marks of the April 1973 flood. A plan and profile of the Aroostook River in Fort Fairfield is shown on Plate 7.

c. Stage Discharge Relations. Stages of floods at Fort Fairfield are a function of not only the magnitude of flows but of the coincidences of ice jams. Normal or "non-ice" stage discharge relationships were first developed using the HEC-2 backwater model. A developed rating curve for the Aroostook River at the Limestone Road bridge in Fort Fairfield is shown on Plate 3. Also shown on Plate 3 is the adjustment to the "non-ice" curve to reflect the probable effect of ice. Adjustments consisted of increasing stages by 1.7 feet based on historic data of ice jams at Fort Fairfield as well as analyses performed at the Washburn gage as discussed in greater detail in paragraph 7d - Stage Frequency Relations.



d. Stage Frequency Relations. Flood stage frequency curves are conventionally determined directly, using developed discharge frequencies and a stage discharge rating for the river. However, because of the history of ice jams on the Aroostook River, stage frequencies were developed by analysis of both peak discharge frequencies and the frequency and magnitude of ice jam flood stages. Normal or "non-ice" stage frequency curves were first developed utilizing the developed peak discharge frequency curves and the "non-ice" stage discharge rating at the Limestone Road bridge in Fort Fairfield. At Fort Fairfield, historic data on ice jam stages is tabulated in Table 7. This historic data indicated that ice jams increased river levels an average of about 3.5 feet over non-ice levels. From inspection of the historic stages at the Washburn gage in Table 6, about 50 percent of the annual peaks were affected by ice. Therefore, the probable ice-affected stage frequency curve, at Fort Fairfield, was assumed mid-way (50 percent) between the non-ice stage frequency curve and the 100 percent ice surcharged curve or the non-ice stage frequency curve was adjusted upward 1.7 feet ($50\% \times 3.5$) to reflect the probable effect of ice. As a comparative check, coincident frequency procedures, as presented in Draft EC1110-2-249, dated 5 June 1985, were also performed and found to be in general conformance with the ice adjusted stage frequency curve. The adopted stage frequency curves are shown on Plate 4.

TABLE 7


HISTORIC ICE JAMS
AROOSTOOK RIVER AT LIMESTONE ROAD BRIDGE
FORT FAIRFIELD, MAINE

| <u>Date</u> | <u>Historic "Ice"</u> <u>High Water</u> <u>(FT-NGVD)</u> | <u>Peak*</u> <u>Discharge</u> <u>(CFS)</u> | <u>"Non-Ice"***</u> <u>High Water</u> <u>(FT-NGVD)</u> | <u>Increase***</u> <u>(FEET)</u> |
|-------------|--|--|--|-------------------------------------|
| 9 Apr 1932 | 362.0 | 28200 | 358.2 | 3.8 |
| 19 Mar 1936 | 363.5 | 51000 | 362.0 | 1.5 |
| 17 Apr 1940 | 362.7 | 41700 | 360.5 | 2.2 |
| 24 Dec 1973 | 361.7 | 25600 | 357.7 | 4.0 |
| 3 Apr 1976 | 365.6 | 43500 | 360.7 | 4.9 |

* Peak Discharge based on coincident peak flow at Washburn gage (DA = 1,654 sq. mi.) transferred to Fort Fairfield (DA = 2,230 sq. mi.) by drainage area ratio.

** Non-ice high water determined from peak discharge and developed "non-ice" discharge rating curve at Limestone Road bridge.

*** Increase in feet of "ice" high water over "non-ice" high water.



SAINT JOHN RIVER BASIN
 AROOSTOOK RIVER
 FORT FAIRFIELD, MAINE
ELEVATION FREQUENCY CURVES
 LIMESTONE ROAD BRIDGE
 (D.A = 2230 SQ. MI.)

8. STANDARD PROJECT FLOOD

a. General. Recommended flood control improvements for the Aroostook River at Fort Fairfield will not provide for Standard Project Flood (SPF) protection; however, an estimated SPF was developed as a "standard" against which the flood potential of the river could be judged, in comparison to the estimated frequency and magnitude of experienced floods. The SPF represents the flood discharge that may be expected from the most severe combination of meteorological and hydrologic conditions that are considered reasonably characteristic of the region excluding extremely rare combinations. The SPF for the Aroostook River at Fort Fairfield was developed by applying standard project storm rainfall to an adopted unit hydrograph generally in accordance with EM 1110-2-1411.

b. Standard Project Rainfall and Snowmelt. Standard project storm rainfall for the watershed above Fort Fairfield was determined from data developed during the Dickey-Lincoln School project studies. Since the Aroostook River is adjacent to and characteristically similar to the Dickey watershed (Saint John River), data developed during these studies were considered applicable for Fort Fairfield. In 1966, a report entitled: "Probable Maximum Precipitation for the Saint John River above Dickey Damsite and between Dickey and Lincoln School Damsites, Maine," was prepared by the Hydrometeorological Branch of the Office of Hydrology, U.S. Weather Bureau, Washington, DC. In this report, probable maximum precipitation (PMP) for six-hour periods and for drainage areas up to 5,150 square miles was presented for the subject basin. Probable maximum storm rainfalls were also developed for various seasons as a percentage of the all-season maximum. It was considered that approximately one-half of the PMP amounts would be appropriate for standard project storm (SPS) estimates for the basin above Fort Fairfield. A spring season (May) SPS rainfall of 4.3 inches in 24 hours was adopted for the watershed above Fort Fairfield. Assuming an infiltration rate of 0.2 inch per 6 hour period, a May SPS excess of 3.5 inches resulted.

In addition to the spring rainfall, snowmelt was considered in determining total SPF runoff. Runoff from snowmelt was determined by the following equation in accordance with EM 1110-2-1406:

$$M = 0.09 + (0.029 + 0.0084 KW + 0.007 R) (T-TF)$$

where

M = daily snowmelt in inches

K = exposure constant (1.0 for unforrested; 0.3 for forrested)

W = wind speed in MPH

R = daily rainfall in inches

T = air temperature in degrees Fahrenheit

TF = snowpack temperature in degrees Fahrenheit (usually 32°F)





Applying the 24-hour SPS rainfall to the above equation, with a 10 MPH wind speed and 49°F air temperature, resulted in a 24-hour snowmelt of 1.52 inches. Therefore, the spring SPS excess of 3.5 inches coincident with a snowmelt of 1.52 inches resulted in a total SPF runoff of 5.02 inches. Six hour rainfall, losses, snowmelts, and excesses are listed in Table 8.

TABLE 8

SPRING SEASON STANDARD PROJECT FLOOD RUNOFF
AROOSTOOK RIVER BASIN
FORT FAIRFIELD, MAINE

| <u>Time</u> <u>(hr)</u> | <u>Rainfall</u> <u>(in)</u> | <u>Loss</u> <u>(in)</u> | <u>Snowmelt</u> <u>(in)</u> | <u>Excess</u> <u>(in)</u> |
|----------------------------|--------------------------------|----------------------------|--------------------------------|------------------------------|
| 0-6 | 2.8 | 0.2 | 0.38 | 2.98 |
| 6-12 | 0.9 | 0.2 | 0.38 | 1.08 |
| 12-18 | 0.3 | 0.2 | 0.38 | 0.48 |
| 18-24 | 0.3 | 0.2 | 0.38 | 0.48 |
| Total | 4.3 | 0.8 | 1.52 | 5.02 |

c. Unit Hydrograph. A unit hydrograph for the Aroostook River at Fort Fairfield was developed by analysis of the April 1973 flood hydrograph at the USGS gaging station in Washburn. In April 1973, coincident with spring snowmelt, 0.87 inch of rain occurred on the 22nd and 23rd followed by 2.18 inches on the 27th thru 29th. The resulting flood hydrograph at Washburn had two distinct peaks on the 24th and 30th, with the latter being the second highest flow of record (see Plate 5). In developing the unit hydrograph, runoff from rainfall on the 22nd and 23rd was subtracted from the total hydrograph and the unit hydrograph was determined for the remaining hydrograph containing 2.4 inches of excess rainfall resulting from the storm on 27 thru 29 April. It is noted that the combination of the earlier storm together with substantial snowmelt during the first few weeks in April produced high antecedent conditions, resulting in a high percentage of rainfall runoff. The 2.4 inch runoff hydrograph had a peak discharge of about 27,000 cfs and was used to determine a 30-hour unit hydrograph. This 30-hour unit graph was then converted to a 6-hour unit graph by standard "s" curve procedures. To adjust the unit hydrograph for Fort Fairfield, Snyder's synthetic unit hydrograph coefficients were determined from the Washburn unit graph and prorated to Fort Fairfield. The resulting 6-hour unit graph at Fort Fairfield had a peak flow of 18,000 cfs and is shown in Plate 5. Pertinent unit hydrograph data are presented in Table 9.



DEPARTMENT OF THE ARMY
 NEW ENGLAND DIVISION
 CORPS OF ENGINEERS
 WALTHAM, MASS.

SAINT JOHN RIVER BASIN
 AROOSTOOK RIVER

FORT FAIRFIELD, MAINE

UNIT HYDROGRAPH ANALYSIS
 APRIL 1973 FLOOD

TABLE 9
AROOSTOOK RIVER
PERTINENT UNIT HYDROGRAPH DATA


| | <u>Washburn</u> | <u>Fort Fairfield</u> |
|---------------------------------|-----------------|-----------------------|
| Drainage Area | 1,654 sq. mi. | 2,230 sq. mi. |
| L | 80 miles | 112 miles |
| L _{ca} | 36 miles | 53 miles |
| T _{ca} | 6 hours | 6 hours |
| T _r | 39 hours | 49 hours |
| C _T ^p | 3.5 | 3.5 |
| C _T ^p 640 | 380 | 380 |
| Q _p | 16,000 cfs | 18,000 cfs |
| q _p | 9.7 cfs/sq. mi. | 8.1 cfs/sq. mi. |


d. Standard Project Flood. The spring season standard project storm rainfall plus snowmelt of 5.02 inches, applied to the adopted 6-hour unit hydrograph at Fort Fairfield, resulted in a spring season standard project flood discharge of 103,300 cfs as shown on Plate 6. The developed standard project flood discharge is about twice the magnitude of the April 1983 discharge of 58,000 cfs. The elevation of the standard project flood at Fort Fairfield would be about 370 feet NGVD or about 4 feet higher than the record April 1976 ice jam related flood or about 7 feet above the non-ice jam related flood of April 1983 flood. A plan and profile of the standard project flood, both with and without improvements, are shown on Plate 7.

9. FLOOD CONTROL IMPROVEMENTS

a. General. Following initial reconnaissance studies, feasible structural improvements for flood control consisted of earth dike flood protection along the rightbank of the Aroostook River within the town of Fort Fairfield. Protection would start about 2,900 feet downstream of the Limestone Road bridge and continue upstream a distance of about 2,700 feet. Improvements were hydrologically sized for the 2 percent chance, 1 percent chance and SPF levels of protection. The 1 percent chance flow with corresponding ice surcharge effect was eventually selected as the design level of protection through the plan formulation process. Properties protected by this dike are predominantly commercial areas along the Aroostook River as shown on Plate 7.

b. Project Design Flood. Based on scoping analyses during DPR studies, the recommended design flood is the 1 percent chance peak flow of 74,000 cfs plus 1.7 ft. allowance for ice jam surcharge. The water surface elevations for the 1 percent chance flow at the downstream and upstream ends of the dike, without ice surcharge, are 364.0 and 365.7 feet NGVD, respectively, and at the Limestone Road bridge is 366.1 feet





NGVD. Water surface elevations were computed by backwater computations using the HEC-2 computer program with a channel Manning's "n" value of 0.03. Flood flow velocities within this reach ranged from 7 to 11 feet per second and are not measurably different from those computed without the project. As a result of the project, the Aroostook River would experience an increase in stage at the Limestone Road bridge of about 0.5 feet. Modified discharge rating curves as well as stage frequency curves, reflecting ice surcharge, are shown on Plates 3 and 4, respectively. Plan and profiles of the 1 percent chance flood with and without ice surcharge as well as the standard project flood are shown on Plate 7.

c. Level of Protection. The proposed plan will provide flood damage protection to properties located along the right bank of the Aroostook River. Top elevation of the dike will be 368.7 feet NGVD at its downstream end sloping uniformly to elevation 370.4 feet NGVD at its upstream end. The design elevations for the top of dike will provide 3 feet of freeboard above the ice surcharged 1 percent chance flood (74,000 cfs plus 1.7 feet increase in stage) level and will be 4.7 feet above the April 1976 flood of record at Fort Fairfield. Similarly, the dike height would provide 3 feet of freeboard above a floodflow 85 percent of the 1 percent chance flood with a coincidental 3.4 feet ice jam surcharge. The selected 3 feet of freeboard above the ice surcharged 1 percent chance flood level will provide some allowance for added ice, debris, or other unpredictable surcharge inducing factors during the design event.

d. Riprap Design. All disturbed earth channel side slopes will be riprap protected. Hydraulic analysis for riprap design was provided by the Hydraulics and Water Quality Section, Water Control Branch using tractive force theories in accordance with EM 1110-2-1601 and ETL 1110-2-120. Riprap was sized with an associated flow depth of 21.4 feet, and for an energy gradient of .00076 foot/foot. Assuming a 1V:2H sideslope, a minimum D₅₀ stone size of 0.35' was determined to resist tractive forces alone. Rock size and layer thickness will be increased to reduce damage expected from ice attack and eddy forces.

e. Alternative Levels of Protection. The following two alternative levels of protection were investigated during DPR studies but were found to provide less total net benefits than the recommended plan.

(1) Two Percent Chance (50-Year Design). In order to provide two percent chance flood damage protection to properties located along the right bank of the Aroostook River, the top elevation of the dike would be 367.7 feet NGVD at the downstream end sloping uniformly to elevation 369.4 feet NGVD at the upstream end, providing 3 feet of freeboard above the ice surcharged 2 percent chance flood (67,000 cfs) level and would be 3.8 feet above the April 1976 flood of record level at Fort Fairfield. Similarly, the dike height would provide about 3 feet of freeboard above a floodflow 82 percent of the two percent chance flood with a coincidental 3.4 foot ice jam surcharge.

(2) Standard Project Flood Design. To provide standard project flood protection, the top elevation of the dike would be 370.1 feet NGVD at its downstream end sloping uniformly to elevation 371.9 feet NGVD at its upstream end. The design elevations for the top of dike would be 1.4 feet higher than for the one percent chance design (recommended plan) and would provide 3 feet of freeboard above the non-ice standard project flood (103,000 cfs) level and is 6.2 feet above the greatest experienced flood level at Fort Fairfield. The SPF design level was not adopted for ice on the thesis that under SPF conditions any ice would go out prior to the occurrence of peak flow.

f. Interior Drainage.

(1) General. The proposed earth dike will intercept runoff from approximately 242 acres of interior area consisting of residential/-commercial areas and farmlands. The interior area was divided into (a) a "high level" watershed of approximately 122 acres which will discharge by gravity via pressure conduit during periods of high flow on the Aroostook River and (b) a "low level" watershed of approximately 120 acres which will drain by gravity during normal periods but will require pumping during high river stages.

(2) High Level Watershed. The high level watershed is situated on the western side of Fort Fairfield consisting of about 60 percent farmlands and 40 percent residential/commercial areas. Runoff from this area flows northerly along the eastern side of the Bangor and Aroostook Railroad and passes through a series of culverts before outletting into the Aroostook River via a 5-foot diameter corrugated metal pipe. Interior drainage requirements for this high level watershed consist of a 48 inch diameter pressure conduit extending from upstream of Main Street to the Aroostook River for a total length of about 350 feet. Top elevation of the headwall above Main Street will be 372.0 feet NGVD, including 2 feet of freeboard, in order to pass the 1 percent chance discharge of 83 cfs against design river stage. This flow capacity is based on the rational formula using a 1 percent chance 1 hour rainfall of 1.9 inches and a runoff coefficient of 0.36. The upstream invert elevation of the proposed pressure conduit will be 366.0 feet NGVD.

(3) Low Level Watershed. The low level watershed is situated in the central part of Fort Fairfield, consisting of about 85 percent moderate business and residential development and 15 percent undeveloped. In the 1960's, a locally constructed channel diverted Libby Brook easterly into Pattee Brook which outlets into the Aroostook River downstream of the proposed line of protection. The remaining undiverted portion of Libby Brook flows through the central part of town and outlets into the Aroostook River through the proposed line of protection via twin 8-foot diameter corrugated metal conduits. Runoff from this low level watershed is conveyed to the Aroostook River by this undiverted portion of Libby Brook. Interior drainage requirements consist of a 48-inch diameter gated gravity conduit, located at the line of protection with capacity to

discharge a minimum of 125 cfs against a normal river stage. The gated gravity conduit should have a slope no less than 0.01 foot per linear foot. This flow capacity is based on the rational formula using a 1 percent chance 1 hour rainfall of 1.9 inches, and a "c" coefficient of 0.55. An interior pumping station will also be required with a capacity of 30 cfs against design river stage. This pumping capacity is equivalent to a runoff rate of 0.25 inch per hour which is comparable to the maximum average hourly rainfall rate during past historic floods, most notably, the April 1973 and April 1983 events. Both the pumping station and gated gravity conduit will be located adjacent to the proposed line of protection just north of Main Street in the vicinity of the present Libby Brook outlet.

SECTION B

GEOTECHNICAL AND DESIGN CONSIDERATIONS

LOCAL PROTECTION PROJECT
ST. JOHN RIVER BASIN
FORT FAIRFIELD, MAINE
GEOTECHNICAL STUDIES

TABLE OF CONTENTS

| <u>Subject</u> | <u>Page No.</u> |
|---|-----------------|
| <u>A. PERTINENT DATA</u> | |
| 1. Purpose | B-1 |
| 2. Location | B-1 |
| 3. Design Flood | B-1 |
| 4. Dike | B-1 |
| 5. Pump Station | B-1 |
| 6. Pressure Conduit | B-1 |
| 7. Railroad Gates | B-1 |
| <u>B. INTRODUCTION</u> | |
| 8. Project Description | B-2 |
| 9. General | B-2 |
| 10. Elevations | B-2 |
| <u>C. TOPOGRAPHY, GEOLOGY AND SEISMICITY</u> | |
| 11. Topography | B-3 |
| 12. Geology | B-3 |
| 13. Seismicity | B-3 |
| <u>D. SUBSURFACE INVESTIGATIONS</u> | |
| 14. Presentation of Data | B-3 |
| 15. Subsurface Explorations | B-3 |
| 16. Future Explorations | B-6 |
| 17. Laboratory Tests | B-6 |
| <u>E. CHARACTERISTICS OF FOUNDATION MATERIALS</u> | |
| 18. Dike | B-7 |
| 19. Gate Structures and Pump Station | B-7 |
| 20. Pressure Conduit | B-7 |
| 21. Groundwater | B-8 |
| 22. Shear Strength and Permeability | B-8 |
| 23. Consolidation | B-8 |

F. CHARACTERISTICS OF EMBANKMENT MATERIALS

| | <u>Page No.</u> |
|-------------------------------------|-----------------|
| 24. General | B-8 |
| 25. Filter Design | B-8 |
| 26. Impervious Fill | B-9 |
| 27. Gravel Bedding | B-9 |
| 28. Stone Bedding | B-9 |
| 29. Stone Protection | B-10 |
| 30. Shear Strength and Permeability | B-10 |
| 31. Sources | B-10 |

G. DESIGN AND CONSTRUCTION

| | |
|-------------------------------------|------|
| 32. Design Criteria | B-11 |
| 33. Materials for Dike Construction | B-11 |
| 34. Dike Sections | B-11 |
| 35. Seepage Control | B-11 |
| 36. Embankment Stability | B-12 |
| 37. Dike Settlement | B-13 |
| 38. Construction Sequence | B-13 |
| 39. Placement and Compaction | B-14 |
| 40. Slope Protection | B-14 |
| 41. Structures | B-14 |
| 42. Environmental | B-15 |
| 43. Access | B-15 |
| 44. Pipelines | B-15 |

Table

No.

| | |
|------------------|-----|
| Probes | B-1 |
| Lab Test Results | B-2 |

Plate

No.

| | |
|-------------------------|-----|
| Exploration Plan No. 1 | B-1 |
| Exploration Plan No. 2 | B-2 |
| Exploration Plan No. 3 | B-3 |
| Engineering Log Profile | B-4 |
| Typical Sections No. 1 | B-5 |
| Typical Sections No. 2 | B-6 |

A. PERTINENT DATA

1. Purpose

Local flood protection

2. Location

State - Maine

County - Aroostook

City - Fort Fairfield

3. Design Flood

Frequency - 100-year flood

Freeboard - 3 feet

D₅₀ - 0.44 feet for 1 vertical to 2 horizontal slope

4. Dike

Type - Earth Fill with Stone Protection

Maximum height above streambank - 28 feet

Maximum height above landside toe - 18 feet

- 16 feet (alternate)

Slopes - Riverside - 1 vertical on 2.5 horizontal

- Landside - 1 vertical on 2.5 horizontal

Total Length - 3,175 feet

- 2,730 feet (alternate)

Top Width - 12 feet to 17 feet (transition sections)

5. Pump Station

Type - Concrete

Bottom Elevation - 342 feet NGVD

Capacity - 30 cubic feet per second

6. Pressure Conduit

Type - Concrete/Dustile Iron

Invert Elevation(s) - 366 feet NGVD to 342 feet NGVD

Diameter - 4 feet

7. Railroad Gates

Type - Stop log

Bottom of footing elevation - 354 feet NGVD

B. INTRODUCTION

8. Location and Description of Project

The proposed flood damage reduction project in Fort Fairfield, Maine is situated on the south bank of the Aroostook River. The Aroostook River originates approximately 61 miles to the southwest of Fort Fairfield at the east outlet of Munsungan Lake in Township 8, Range 9, Maine. It flows in a northeasterly direction after passing through Fort Fairfield approximately 9 miles to its confluence with the St. John River in Four Falls, New Brunswick, Canada. The project will consist of a 3,175 or 2,730 foot (alternate) foot earth dike situated on the south bank of the Aroostook River, a pump station and pressure conduit to handle interior drainage, and two railroad gates to provide end closures for the dike. The project will reduce flood damage to private and commercial properties in the Fort Fairfield central business district during large flood events.

9. General

Subsurface investigations and geotechnical engineering studies were performed to further the continued planning of structural features to reduce flood damage in Fort Fairfield, Maine. The subsurface investigations included research of available information, geological studies, subsurface explorations and laboratory testing. The subsurface investigations were performed to determine the distribution and description of potential foundation materials for the proposed improvements. Preliminary geotechnical engineering studies, based on the data collected from the subsurface investigations were conducted to develop safe and economical preliminary foundation designs, dike sections, and construction methods.

Additional Plan Formulation was done after completion of subsurface investigations and most of the geotechnical engineering effort for this report. Changes due to the additional plan formulation are designated as "alternate" on the plates and in the text. Subsurface explorations and geotechnical studies will be required during the plans and specifications stage to accommodate the alternate pump station and south gate structure locations.

10. Elevations

All elevations mentioned in this report are in reference to the National Geodetic Vertical Datum (NGVD), which is the mean sea level of 1929.

C. TOPOGRAPHY, GEOLOGY AND SEISMICITY

11. Topography

The project site is on the south bank of the Aroostook River about nine river miles southwest from its confluence with the St. John River in New Brunswick, Canada. The centerline of the proposed dike is along a sloping river bank which averages about 80 feet wide and varies in elevation (El.) from approximately 340 feet to 360 feet. Terraces are well developed on the opposite bank of the river. Away from the river banks, low, rounded hills rise to about El. 700 feet.

12. Geology

The bedrock of the area is mapped as the Spragueville Formation, a calcareous metasiltstone with interbedded silty limestones. Borings along the alignment went to elevations as low as El. 327 feet with none reaching bedrock, but State of Maine Route 165 highway bridge borings reached bedrock as shallow as El. 345 feet where the railroad passes under the highway bridge just upstream of the project site. The borings show that the rock surface plunges as deep as El. 270 feet toward the north bank of the river, or about 75 feet below the water surface. Along the dike alignment the overburden consists of fill, sands and gravels with minor silts which overlie a sandy gravelly till.

13. Seismicity

The project is located in Seismic Zone 1 as defined by the map contained in Engineering Regulation, ER 1110-2-1806, "Earthquake Design and Analysis for Corps of Engineers Projects." A seismic coefficient of 0.05g is to be used for stability analyses of concrete structures.

D. SUBSURFACE INVESTIGATIONS

14. Presentation of Data

Locations of the subsurface explorations are shown on Plates B-1, B-2, and B-3. An Engineering-Log Profile of the borings is presented on Plate B-4. Probe data is shown on Table B-1. The results of soil tests are included in Table B-2.

15. Subsurface Explorations

Atlantic Testing Laboratories, Limited executed seven hollow stem auger borings (FD-86-7 to FD-86-13) for the United States Army Corps of Engineers (USACE), March 10-12, 1986. The boreholes were advanced in areas where proposed structures are to be constructed. Standard Penetration Tests and split spoon samples were generally taken at 5-foot intervals or more frequently when required by the inspector. The test borings were terminated at depths from 12 feet to 32 feet.

TABLE B-1


PROBES

| FP NO. | 1 | 2 | 3 | 4 | 5 | 6 |
|------------------------|----|----|----|----|----|----|
| DEPTH OF PROBING (FT.) | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| 1 | | | | | | |
| 2 | 28 | 20 | 13 | | 16 | |
| 3 | 60 | 37 | | | 28 | 49 |
| 4 | R | R | 27 | 34 | R | R |
| 5 | | | R | R | | |
| 6 | | | | | | |

LEGEND


| | |
|----|---|
| | One man pushing |
| | Two men pushing |
| 40 | Actual blows using 8 pound sledge for depth shown |
| R | Refusal determined by bending or breaking of probing gear |

Note: All probings used 3/4" pipe



BORING PLAN

SCALE IN HUNDREDS OF FEET



INTERPRETIVE GEOLOGIC SECTION

HORIZ. 1" = 100'
SCALE VERT. 1" = 10'

LEGEND

- ◀ Subsurface water level
- NS Not sampled
- 22 Representative blow count using a 350 lb. hammer with fall of 18 inches
- * Blow count not considered representative
- SM Graphic symbol according to Unified Soil Classification System
- ◻ Cobble or boulder (Core drilled)
- ◻ Nested boulders or cobbles
- A — A Line of Cross-Section
- FD Foundation drill hole
- FP Foundation probe

| FP NO. | 1 | 2 | 3 | 4 | 5 | 6 |
|-----------------------|----|----|----|----|----|----|
| DEPTH OF PROBING (FT) | 1 | 2 | 3 | 4 | 5 | 6 |
| 1 | 28 | 20 | 13 | 16 | 28 | 49 |
| 2 | 60 | 37 | 27 | 34 | R | R |
| 3 | R | R | R | R | R | R |


Note: All probings used 3/4" pipe.

HAND PROBING TABLE (FP)


NOTES:



Test borings FD-1 thru FD-3 made by the Corps of Engineers 10-12 July 1950.
Test borings FD-4 thru FD-6 made by the Corps 27 September thru 4 October 1978.
Hand probings were made by the Corps on 6 October 1978.

GRAPHIC SCALES




| | |
|--|---|
| DEPARTMENT OF THE ARMY NEW ENGLAND DIVISION CORPS OF ENGINEERS WALTHAM, MASS. | |
| RJD | ST. JOHN RIVER BASIN STUDY |
| RJD | AROOSTOOK RIVER WATERSHED AT FORT FAIRFIELD, MAINE |
| CGH | BORING AND PROBING DATA |
| GEOTECH. ENG. BR. | SCALE: AS SHOWN |
| PLATE I | DATE: 3 MAY 1983 |






PLAN
SCALE: 1"=40'

NOTE: For notes and legend see plate



TYPICAL SECTION
FROM STA 7+50 TO STA 16+00
SCALE: 1"=10'-0"



TYPICAL SECTION
FROM STA 16+00 TO STA 26+00
SCALE: 1"=10'-0"




DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION
CORPS OF ENGINEERS
WALTHAM, MASS.

ST. JOHN RIVER BASIN
LOCAL PROTECTION PROJECT
AROOSTOOK RIVER
FORT FAIRFIELD, MAINE
PLAN AND SECTIONS NO2

SCALE: AS SHOWN

DATE: MAR. 1987




PLAN
SCALE: 1"=40'


NOTE
FOR NOTES AND LEGEND SEE PLATE

RIVERSIDE

LANDSIDE



TYPICAL SECTION
FROM STA. 26+00 TO END OF DIKE
SCALE: 1"=10'-0"



DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION
CORPS OF ENGINEERS
WALTHAM, MASS.

**ST. JOHN RIVER BASIN
LOCAL PROTECTION PROJECT**

AROOSTOOK RIVER
FORT FAIRFIELD, MAINE

GENERAL PLAN AND SECTIONS NO. 3

SCALE: AS SHOWN

DATE: MAR. 1987

TABLE B-2

SOIL TESTS RESULTS

| EXPL. NO. | TOP ELEV. FT. | SAMPLE NO. | DEPTH FT. | SOIL SYMBOL | MECHANICAL ANALYSIS | | | | ATT. LIMITS | | SPECIFIC GRAVITY | NAT. WATER CONTENT % DRY WT | | COMPACTION DATA | | | NAT. DRY DENSITY LBS/CUFT | | OTHER TESTS | | |
|--------------|---------------------|---------------|--------------|----------------|------------------------|-----------|------------|------------------------|----------------|----|---------------------|-----------------------------------|-------|---------------------------|--------------------------------|-----------------------|---------------------------------|-------|----------------|---------|-------|
| | | | | | GRAVEL % | SAND % | FINES % | D ₁₀ mm. | LL | PL | | TOTAL | - NO4 | OPT. WATER % DRY WT | MAX. DRY DENS. LBS/CU FT | * PVD LBS/CU FT | TOTAL | - NO4 | SHEAR | CONSOL. | PERM. |
| | | | | | | | | | | | | | | | | | | | | | |
| FD-78-4 | 352.0 | J3 | 2.7-5.0 | CL-ML | 0 | 40 | 60 | 0.003 | 27 | 21 | | 35.5 | | | | | | | | | |
| FD-78-4 | 352.0 | J7-1 | 6.7-10.2 | CL | 0 | 30 | 70 | 0.005 | 31 | 22 | | 27.9 | | | | | | | | | |
| FD-78-4 | 352.0 | J7-2 | 6.7-10.2 | CL | 0 | 0 | 96 | 40.001 | 27 | 19 | | 22.2 | | | | | | | | | |
| FD-78-4 | 352.0 | J13 | 15.0-16.2 | SC | 5 | 65 | 30 | 0.015 | | | | | | | | | | | | | |
| FD-78-4 | 352.0 | J14 | 16.2-19.4 | SC | 38 | 40 | 22 | 0.025 | | | | | | | | | | | | | |
| FD-78-4 | 352.0 | J16 | 20.0-24.5 | GC | 55 | 30 | 15 | 0.03 | | | | | | | | | | | | | |
| FD-78-5 | 351.0 | J 7 | 5.6-10.0 | GP-GM | 59 | 34 | 7 | 0.3 | | | | | | | | | | | | | |
| FD-86-7 | 361.0 | S-3 | 10.0-12.0 | SW-SM | 24 | 69 | 7 | 0.2 | | | | | | | | | | | | | |
| FD-86-8 | 361.0 | S-3B | 11.5-12.0 | SM | 1 | 67 | 32 | - | | | | | | | | | | | | | |
| FD-86-8 | 361.0 | S-4 | 15.0-17.0 | SM | 1 | 71 | 28 | - | | | | | | | | | | | | | |
| FD-86-9 | 363.0 | S-4 | 15.0-17.0 | GM | 47 | 40 | 13 | - | | | | | | | | | | | | | |
| FD-86-10 | 361.0 | S-2 | 5.0-7.0 | SM | 22 | 63 | 13 | - | | | | | | | | | | | | | |

Three drive sample borings (FD-78-4 to FD-78-6) and six hand probes (FP-78-1 to FP-78-6) were performed and inspected by the USACE from September 27, 1978 to October 6, 1978. The borings were terminated at 25 feet of depth along the centerline of the proposed dike. Continuous sampling was performed in the boreholes by driving 2-1/2-inch and 2-inch inside diameter solid spoons with a 350 pound weight and 18-inch drop except where diamond core drilling was required to penetrate obstructions. The hand probes were advanced near the normal Aroostook River water line with an eight pound sledge to depths from 2.6 feet to 3.2 feet.

The Maine State Highway Commission performed 13 drive sample explorations for the Aroostook River bridge which is approximately 500 feet north (upstream) of the proposed dike. The explorations varied in depth from 20.0 feet to 88.8 feet. Solid tube samples were generally taken at 5-foot intervals. Rock was cored in 12 of the holes.

Three preliminary drive sample borings (FD-50-1 to FD-50-3) were executed and inspected by USACE, July 10-12, 1950. The borings were located along the existing Canadian Pacific Railroad main line track which is from 90 feet to 175 feet west (inland) of the proposed dike. The depth of the borings varied from 15.5 feet to 31.0 feet. Continuous sampling was performed in the boreholes by driving 2-1/2-inch and 2-inch inside diameter solid spoons with a 350 pound hammer and 18-inch drop.

16. Future Explorations

The south gate structure and pump house will be moved to the alternate locations shown on Plates B-1 and B-3. It is recommended that explorations be performed at their alternate locations during plans and specifications stage to identify the depth of firm undisturbed natural materials. It also is recommended that test pits be executed during plans and specifications stage to better define the extent of the rubble fill near FD-78-6, the soft clayey silts, sands, and gravels near FD-78-4, and the location of utility lines.

17. Laboratory Tests

All laboratory tests were performed in accordance with the procedures described in Corps of Engineers Manual EM 1110-2-1906, "Laboratory Soils Testing." All soil samples were visually classified in accordance with the Unified Soil Classification System. Grain size analyses, Atterberg Limit determinations, Hydrometer analyses, and Moisture Content determinations were performed on selected samples to help classify the materials encountered and to provide more precise data where required.

E. CHARACTERISTICS OF FOUNDATION MATERIALS

18. Dike

Most of the riverside toe of the dike will lie in the pool (normal water El. 352 feet) created by Tinker Dam which is located approximately one mile downstream. The six probes taken in the proposed toe area indicate that the depth to firm ground is 12 to 18 inches. The soil profile under the proposed dike, is granular fill underlain by silty sandy gravels (GM) and silty gravelly sands (SM). Exceptions to the profile were observed near FD-78-6 where rubble fill was encountered and FD-78-4 where clayey silts, sands, and gravels were observed beneath the fill.

The fill is a brown to dark brown, heterogeneous mixture of silt, sand and gravel with cinders, organic matter, brick fragments, porcelain fragments, glass, roots, concrete, tar paper, steel rods, cobbles, boulders and sometimes having an organic odor. The observed thickness of the fill varies from 1.5 feet to 22.0 feet. Blow counts recorded during standard penetration tests and solid spoon drives indicate the fill is very loose to very compact.

Light brown, brown and gray-brown silty sandy gravels (GM) and silty gravelly sands (SM) were observed below the fill. The silt content varied from 7 to 32 percent in grain size determinations performed on the silty sandy gravels and silty gravelly sands. Standard Penetration test and solid spoon sample blow counts indicate the silty sandy gravels and silty gravelly sands are very loose to very compact. Most of the very loose materials are near the top of the silty sandy gravel and silty gravelly sand layer.

19. Gate Structures and Pump Station

The soil profile beneath the gates structures and pump station is similar to the one beneath the dike. The fill thickness is 5.0 feet to 11.5 feet at the proposed north gate structure, 15.0 feet at the proposed pump station, and 0 feet to 5.0 feet at the proposed south gate structure.

20. Pressure Conduit

The soil profile along the proposed pressure conduit is granular fill underlain by a brown, sandy silt. The granular fill varies 0 feet to 4.0 feet in thickness and is similar to the fill material below the proposed dike embankment. The brown, sandy silt is nonplastic. It is loose to moderately compact in consistency based on standard penetration test results.

21. Groundwater

Groundwater was encountered in the boreholes from El. 348 feet to El. 351 feet except for FD-78-6 and FD-86-13 where none was observed, FD-86-11 (El. 343 feet), and FD-86-12 (El. 361 feet). It must be noted that fluctuations in the groundwater levels may occur because of variation in rainfall, snow, ice, temperature, or other factors which differ from the conditions present at the time the observations were made.

22. Shear Strength and Permeability

Shear strength and permeability tests were not performed on the foundation soils. The estimated angle of internal friction for the foundation soils is 28 to 30 degrees. The estimated coefficient of vertical permeability for the foundation soils is $(0.3 \text{ to } 3) \times 10^{-4} \text{ cm/s}$. The estimates are based on visual examination of the samples, grain-size distribution curves, data from exploration logs and experience with similar materials.

23. Consolidation

Consolidation tests were not performed on samples of foundation soils. All soft and compressible surficial materials will be removed prior to the construction of the dike embankment. The consolidation characteristics and natural densities of the principally granular foundation soils beneath the surficial materials are such that significant post-construction foundation settlement is not anticipated under the proposed embankment loadings.

F. CHARACTERISTICS OF EMBANKMENT MATERIALS

24. General

Most of the materials from the required stripping and excavation operations will not be suitable for use in construction of the dike embankment. The suitable material from the excavation and stripping operations will be used to the extent practicable. The contractor will furnish all embankment materials other than those available from the required excavation and stripping operations due to the high cost of developing government furnished borrow areas and difficulty involved in acquiring the land for borrow areas.

25. Filter Design

The gradation requirements for impervious fill, gravel bedding, stone bedding, and stone protection have been established in accordance with the filter criteria set forth in Engineering Manual, EM 1110-2-1913, "Design and Construction of Levees."

26. Impervious Fill

Impervious fill will be furnished by the contractor. It will be a natural, reasonably well graded, unprocessed material which contains clay, silt, and sand. Experience with materials meeting the gradation ranges below indicates that placement moisture contents can be maintained within two percent of optimum moisture content with moderate control and that in-place dry densities will be approximately 135 pounds per cubic foot.

| <u>Sieve Size</u> <u>(U.S. Std.)</u> | <u>Percent Passing</u> <u>by Dry Weight</u> |
|---|--|
| 6-inch | 100 |
| 3-inch | 85-100 |
| No. 4 | 70-95 |
| No. 40 | 35-70 |
| No. 200 | 20-45 |

27. Gravel Bedding

Gravel Bedding will be furnished by the contractor. It shall consist of tough, durable particles of sand and gravel or crushed stone which are reasonable well rounded. The materials shall be reasonably well graded within the limits specified below.

| <u>Sieve Size</u> <u>(U.S. Std.)</u> | <u>Percent Passing</u> <u>by Dry Weight</u> |
|---|--|
| 6-inch | 100 |
| 1-inch | 50-90 |
| No. 4 | 25-75 |
| No. 16 | 15-50 |
| No. 200 | 0-5 |

(In addition, not more than 10 percent, by dry weight, of the component passing the No. 4 sieve shall pass the No. 200 sieve.)

28. Stone Bedding

Stone bedding will be furnished by the contractor. It shall consist of quarried rock, composed of hard, durable, angular and sound rock fragments. Stone bedding shall be reasonably well graded within the limits specified below.

| <u>Sieve Size</u> <u>(U.S. Std.)</u> | <u>Percent Passing</u> <u>by Dry Weight</u> |
|---|--|
| 6-inch | 90-100 |
| 1-1/2 inch | 0-40 |
| No. 4 | 0-5 |

29. Stone Protection

Stone protection will be furnished by the contractor. It shall consist of quarried rock, composed of hard durable, angular and sound rock fragments with a unit weight of not less than 162 pounds per cubic foot. It shall meet the following gradation and size requirements.

| <u>Class</u> | <u>Limits of Stone Weight (Pounds)</u> | <u>Percent Lighter by Weight</u> |
|--------------|--|--------------------------------------|
| I | Between 120 and 300 (Max) | 100 |
| | Between 60 and 90 | 50 |
| | Less than 20 | 15 |
| | 2 (Min.) | 0 |
| II | Between 900 and 2300 (Max.) | 100 |
| | Between 450 and 700 | 50 |
| | Less than 150 | 15 |
| | 2 (Min.) | 0 |

30. Shear Strength and Permeability

It is estimated based on the above gradations that the proposed embankment materials will develop the following angles of internal friction and coefficients of permeability:

| <u>Materials</u> | <u>Angle of Internal Friction (Degrees)</u> | <u>Coefficient of Permeability (cm/s)</u> |
|----------------------|---|---|
| Compacted Impervious | 30 + 32 | $<10^{-4}$ |
| Dumped Gravel | 30 to 33 | 10^{-3} to 10^{-2} |
| Compacted Gravel | 35 to 37 | 10^{-3} to 10^{-2} |
| Gravel Bedding | 35 to 37 | 10^{-3} to 10^{-2} |
| Stone Bedding | 40 | $>10^{-2}$ |
| Stone Protection | 40 | $>10^{-2}$ |

31. Sources

Sand, gravel, and stone could be supplied by a commercial supplier in Presque Isle which is approximately 10 miles from the proposed project site. Private sand, gravel, and stone sources exist along the Aroostook River within 5 miles of the project which have been opened for use on past projects. Concrete is available from the suppliers in Presque Isle, Houlton, and Madawaska which are all within 40 miles of the site.

G. DESIGN AND CONSTRUCTION

32. Design Criteria

The principles and procedures discussed in Engineering Manual, EM 1110-2-1913, "Design and Construction of Levees," were used to develop dike sections for this project. Layer thicknesses and stone sizes for the proposed stone protection on the dike were determined using procedures in the Engineering Manual, EM 1110-2-1601, "Hydraulic Design of Flood Control Channels" and Engineering Technical Letter, ER 1110-2-120, "Additional Guidance for Riprap Channel Protection."

33. Materials for Dike Construction


All dike materials will be furnished by the contractor. It is estimated that approximately 2,000 cubic yards of excavation will be required to remove unsatisfactory dike foundation materials. Most of the material excavated will not meet the specifications for the dike embankment materials. The Contractor will be required to dispose of the excavated material that can not be reused at an appropriate upland site.

34. Dike Sections


Proposed dike sections are shown on Plates B-5 and B-6. The shape of the sections was influenced by foundation conditions, seepage control requirements, river erosion, ice action, maintenance considerations, and construction sequence. The stone protection thickness is greater in Section A-A (Typical End Section) than the other sections to reduce erosion caused by eddy currents and ice action at the ends of the dike. The toe on the landside of the dike will interrupt seepage in critical areas and act as an inspection trench during construction. Stone will protect the dike from erosion and ice action on the riverside. Grass, placed at a 1 vertical on 2.5 horizontal slope for maintenance reasons, will protect the landside dike slope. The dumped gravel fill riverside berm will expedite construction of the dike and will allow the contractor to dewater the central dike base prior to placing the compacted impervious fill core. The compacted impervious fill core will cut off seepage.

35. Seepage Control

The design hydrostatic head for the dike is the difference between the 100-year flood level (El. 366 feet to El. 367 feet) on the waterside and a water level at the ground surface on the landside. The design hydrostatic head ranges from approximately 3 feet to approximately 15 feet. Seepage through the dike will be controlled by the relatively long seepage path through the impervious core. Foundation seepage will be controlled by the relatively long seepage path through the predominantly silty sandy gravel and silty gravelly sand foundation soils. A shallow landside toe drain will be provided to interrupt seepage and reduce softening on the inside of the dike.



SECTION A-A
TYPICAL FROM STA. 0+00 TO STA. 3+00 AND STA. 28+75 TO STA. 31+75




SECTION B-B
TYPICAL FROM STA. 3+00 TO STA. 7+50

NOTES:

1. Dike sections are designed for 100-Year Flood Level and include 3-foot freeboard.
2. All pipes shall be removed from beneath the dike.
3. Existing riverbank slopes shall be cut to 1 vertical on 2 horizontal or flatter.
4. Assume 1 foot of stripping to the Landside of the dumped gravel fill.
5. Assume 2000 cubic yards of trash and debris will be excavated and disposed of off site, in addition to the stripping.
6. Top of bascule gate at Tinker Dam is located approximately 1 mile downstream, is El. 352.0.




| |
|--|
| DEPARTMENT OF THE ARMY NEW ENGLAND DIVISION CORPS OF ENGINEERS WALTHAM, MASS. |
| WATER RESOURCES DEVELOPMENT PROJECT FORT FAIRFIELD, MAINE |
| LOCAL PROTECTION PROJECT TYPICAL SECTIONS NO. 1 |
| AROOSTOOK RIVER |




NOTE:
Notes are shown on PLATE B-5

SECTION C-C
TYPICAL FROM STA. 7+50 TO STA. 16+00



SECTION D-D
TYPICAL FROM STA. 16+00 TO STA. 28+75



DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION
CORPS OF ENGINEERS
WALTHAM, MASS.

WATER RESOURCES DEVELOPMENT PROJECT
FORT FAIRFIELD, MAINE

LOCAL PROTECTION PROJECT
TYPICAL SECTIONS NO. 2

AROOSTOOK RIVER MAINE

36. Embankment Stability

Section D-D was selected for stability analysis because it combines maximum embankment height with average to low foundation strengths. Section D-D was analyzed for stability against shear failure using circular failure surfaces and the UTEXAS2 slope stability package for the End of Construction, Sudden Drawdown from Maximum Pool, Intermediate Flood Stage, Steady Seepage from Maximum Pool conditions. An analysis of earthquake conditions was not judged necessary due to the height of the dike, the low magnitude of earthquakes that have occurred in the vicinity of the site in the past, and the characteristics of the dike materials. The design unit weights and shear strength parameters were selected on the basis of experience with similar materials on other projects and are tabulated below:

| Material | Unit Weight (pcf) | | Shear Strength (degrees, psf) | | |
|---|-------------------|-------|-------------------------------|------|------|
| | saturated | moist | Q | R | S |
| Stone Protection | 135 | 118 | 40,0 | 40,0 | 40,0 |
| Gravel Bedding and Compacted Gravel Fill | 145 | 135 | 35,0 | 37,0 | 37,0 |
| Dumped Gravel Fill | 135 | 120 | 30,0 | 33,0 | 33,0 |
| Compacted Impervious Fill | 140 | 135 | 30,0 | 30,0 | 32,0 |
| Foundation Soils (above El. 342.0 feet) | 137 | 130 | 28,0 | 28,0 | 30,0 |
| Foundation Soils (Below El. 342.0 feet) | 140 | 133 | 30,0 | 30,0 | 32,0 |

The minimum factor of safety for each condition is shown below. The results indicate that the selected embankment is safe from shear failure.

| Condition | Factor of Safety | | |
|---|------------------|------------|--------|
| | Acceptable | Calculated | |
| | | (Shallow) | (Deep) |
| End of Construction (Riverside) | 1.3 | 1.6 | 1.5 |
| End of Construction (Landside) | 1.3 | 1.4 | 2.0 |
| Sudden Drawdown from Maximum Pool (El. 367) | 1.0 | 1.3 | 1.2 |
| Intermediate Flood Stage (El. 360 and El. 356) | 1.4 | 1.6 | 1.6 |
| Steady Seepage from Maximum Pool (El. 367) | 1.4 | 1.5 | 1.7 |

37. Dike Settlement

The embankment and foundation soils are of low compressibility except possibly for the rubble fill near FD-78-6 and the clayey silts, sands, and gravels near FD-78-4. The rubble fill and surficial, soft, clayey silts, sands and gravels will be removed prior to construction of the dike. The remaining clayey silts, sands and gravels are judged to be of low compressibility in situ due to their high densities and low plasticity indices. Therefore, it is expected that all significant settlement of the principally granular embankment and foundation soils will occur during construction.

38. Construction Sequence

The dumped gravel fill riverside toe will be constructed starting at the upstream end by pushing material into and down the Aroostook River with bulldozers. The riverside toe will act as a cofferdam and will facilitate dewatering of the compacted fill areas by open pumping. Deleterious materials will be stripped in the compacted fill areas after completion of dewatering and prior to placement of fills. Compacted fills will be placed to their full width in reaches long enough to permit proper operation of compaction equipment. Stone protection and bedding layers will be placed below normal water without diversion or dewatering of the construction area immediately after completion of the dumped gravel fill riverside toe. Above normal water, they will be placed in the dry after completion of the compacted fills. Dike reaches will be completed to their full width including stone protection prior to flood season.

39. Placement and Compaction

Compacted gravel and impervious fill materials will be spread with bulldozers or other approved equipment in loose layers of 8 inches in non-restricted areas and 4 inches in restricted areas. Each layer will be compacted to 95 percent of its maximum dry unit weight as determined by modified proctor test ASTM D-1557. Heavy tractors and vibratory rollers will not be allowed in restricted areas.

40. Slope Protection

Hydraulic analysis for erosion control of the dike indicates that a minimum D_{50} stone size of 0.44 feet is adequate to resist tractive forces for a 1 vertical to 2 horizontal slope. A stone layer thickness of 0.75 feet was calculated from the minimum D_{50} stone size. The stone layer thickness was increased to 1.5 feet for placement above normal water to resist ice forces, and to 2.25 feet for placement below normal water to resist ice forces and to provide for uncertainties associated with underwater placement. The stone sizes required to construct layers 1.5 feet and 2.25 feet thick will be large enough to be considered vandal proof.

Experience with ice action at Fort Kent, Maine has shown embankment displacements occur in the transition areas even when twice the minimum D_{50} stone size is used to determine the layer thickness. Three times the minimum D_{50} stone size was used to calculate a stone layer thickness of 2.25 feet in the transition areas. The stone layer thickness in the transition areas were increased to 3.0 feet for placement above normal water to resist ice forces, and to 4.5 feet for placement below normal water to resist ice action and to provide for uncertainties associated with underwater placement.

The proposed classes and gradations for the stone protection are listed in Section 29. The proposed stone protection sections are shown on Plates B-5 and B-6.

41. Structures

A pump station, pressure conduit and two railroad gates will be appurtenant structures to the dike. They will be light weight structures constructed at the locations shown on Plates B-1 to B-3. They will be constructed on undisturbed natural soils or compacted gravel fill placed on undisturbed natural soils, and at least 6 feet below grade for adequate frost protection. The proposed bottom elevations for the structures are 354 feet for the gates, 348 feet for the pump station, and from 366 feet to 342 feet for the pressure conduit.

A design bearing pressure of 4000 pounds per square foot will be used to design the spread footings required for the gates and pump house. Design bearing pressures for footings less than three feet in minimum

dimension will be reduced to B/3 times the recommended bearing pressure, where B is the smallest dimension of the footing in feet. A minimum width of 18 inches will be maintained for continuous footings.

42. Environmental

The environmental concerns identified to date are: movement of pesticides in the river bottom sediments during construction of the river side toe, disposal of stripped material and rubble fill, migration of fines downstream during the dewatering operation, and a petroleum odor in exploration FD-86-11. The results of an Impact Analysis Branch Sampling and Testing Program conducted during the winter and spring of 1986 indicate the levels of pesticides are not high enough in the river bottom sediments at the site to be concerned that significant amounts will move during construction. It is recommended that additional testing be performed during construction to insure pesticide movement is minimal. The town of Fort Fairfield and the state of Maine will identify appropriate disposal areas for the stripped material and rubble fill. Silt curtains or an alternative will be used to reduce migration of fines downstream during the dewatering operation. The downstream end of the dike will be moved to avoid possible contaminated materials in the vicinity of exploration FD-86-11.

43. Access

A gravel surface access road will run along the crown of the dike to allow for inspection, maintenance, recreation and flood-fighting activities. Either two access ramps and one turnout or one access ramp, one turnout, and turnaround will be provided to facilitate use of the access road. Locations for the access ramps, turnout, and turnaround will be decided during the plans and specifications stage.

44. Pipelines

One 16-inch sewer main and many smaller live and abandoned utility pipes exist under the proposed dike alignment. The sewer main and line utility lines will be moved outside the dike limits. The abandoned utility pipes will be removed prior to construction of the dike. The inspection trench and test pits will be used to search for lines that may not have been identified.

SECTION C

STRUCTURAL DESIGN

DETAILED PROJECT REPORT
FORT FAIRFIELD LOCAL PROTECTION
FORT FAIRFIELD, MAINE

STRUCTURAL DESIGN REPORT

1. Purpose: The purpose of this report is to facilitate the review by a higher authority of the structural design features of the Fort Fairfield Local Protection Project, Fort Fairfield, Maine. This information is presented for inclusion in the Detailed Project Report, prepared under the special continuing authority of Section 205 of the 1948 Flood Control Act, as amended.
2. Introduction: This section presents the criteria, data, and assumptions used for the structural design of the proposed structure for this project. A brief description of each structure is provided and followed by stability computations designed to investigate the critical design condition.
3. Criteria Documents: Structural design criteria are contained in the publications listed below:

CORPS OF ENGINEER PUBLICATIONS

- EC 1110-2-510 "Working draft of the Retaining and Flood Wall Manual", 31 August 1983 with Changes 15 July 1985.
- ETL 1110-2-256 "Sliding Stability of Concrete Structures" 24 Jun 1983.
- EM 1110-2-2501 "Flood Wall Manual" January 1948.

4. MAJOR STRUCTURAL FEATURES:

The project ^{includes} involves two concrete stop-log structures, a pumping station and a ^{4-foot diameter Ductile Iron} pressure conduit. The pressure conduit requires an inlet head wall, an outlet structure, and an emergency gate well. The gravity discharge conduit at the pumping station also requires a sluice gate well.

The following structures were analyzed for stability:

- | | |
|------------------------------------|-----------------------------|
| a. Stop-log structure / Downstream | <u>Appendix A</u> page 1 |
| b. Stop-log structure / Upstream | page 9 |
| c. Pressure-conduit Inlet headwall | page 15 |
| d. Pumping station | page 19 |

Each Set of stability computations provides a description of the structure, the design criteria and parameter values used in the calculations. The final design concepts of all the structural features of the job are presented in Plates (C1 - C4) of this report.

5. WORK TO BE COMPLETED: During the preparation of plans and specifications, the detailing of all watertight joints, reinforcement and equipment installation can be designed.

Special attention should be given to the design of the 48" Ductile Iron pressure conduit. At any point under the main body of the dike, the conduit is under about a 29-foot head during an extreme flood condition. Pipe connections should be designed to withstand this pressure. An emergency gate well with a slide-type flap gate was designed to prevent excessive pressures resulting due to a river backflow condition. The flap gate would also allow for the interior drainage operation of the conduit during a flood condition.

27 Sept 49

SUBJECT

FORT FAIRFIELD - MAINE LPP

COMPUTATION

STOP LOG - STRUCTURE / DOWNSTREAM

COMPUTED BY

ENestorides

CHECKED BY

DATE

2-6-87


FORT FAIRFIELD - STOP LOG STRUCTURE / DOWNSTREAM

The stop log structure is a concrete U-channel with a center post and 2 bays of stoplogs. The opening is about 35 feet wide and positioned on a skew with respect to the dike center line. On either end of the stop log structure concrete gravity walls extend to retain the dike embankment [See plan below].

The structures primary function as a retaining wall and was designed in accordance to the following Corps Design Criteria:

1. EC 1110-2-510: "Working Draft of the Retaining and Flood Wall Manual" 31 August 1983 (w/changes 15 July '85)
2. EM 1110-2-2501: "Flood Wall Manual" January 1948 (w/changes)
3. ETL 1110-2-256: "Sliding stability of Concrete Structures" 24 Jan 64

The stop log structures and adjoining walls are shown in plan below:



There will be no sheet pile cutoff under the stop log structure nor a cut-off wall into the dike due to the low differential head and the long line of creep.

$$\Delta h = 5 \text{ ft}$$

Creep Ratio: along wall $\frac{57 \text{ ft}}{5} \Rightarrow 11.4 > 4$ (permissible for sands & gravels) OK ✓

under stoplogs $\frac{32 \text{ ft}}{8} \Rightarrow 4.4 > 4$ OK ✓

SUBJECT

FORT FAIRFIELD - MAINE LPA

COMPUTATION

STOP LOG STRUCTURE / DOWNSTREAM

COMPUTED BY

ENestorides

CHECKED BY

DATE 2/6/87

DESIGN METHOD

One section of the concrete U-channel and two typical sections of the gravity wall will be analyzed for stability under one load case. Load Case R2 was used for each section since it represents a rapid drawdown situation which is an extreme loading for retaining structure. Since the area in question is in seismic zone one (minor damage) the earthquake condition is not critical.

All the structures are founded on compacted gravel fill and under Load Case R2, they must satisfy the following stability criteria:

- 75% of the base must be in compression,
- the factor of safety against sliding must be greater than 1.33,
- and c) bearing pressures should not exceed the allowable $4k/ft^2$.

Design & Soil Parameters:

| | kct | | | ϕ | assume C / ϕ |
|---|------------------|----------------------|----------------------|--------|----------------------|
| | γ_{moist} | $\gamma_{saturated}$ | $\gamma_{submerged}$ | | |
| Dumped Gravel bedding (RR) | .120 | .135 | .073 | 32° | 0 / 0° |
| Compacted Impervious Foundation soil | .135 | .140 | .078 | 30° | 0 / 0° |
| | .130 | .137 | .075 | 28° | 0 / 0° |

- Allowable bearing capacity for foundation $2T/ft^2 \Rightarrow 4k/ft^2$ [GEB]
- Min. Frost Penetration depth required \Rightarrow 6 feet
- Consider Soil pressures using K_0 (at rest)

$$K_0 = 1 - \sin \phi \text{ (Jaky's formula)}$$

$$\phi = 30^\circ$$

$$K_0 = 1 - .5 \Rightarrow K_0 = .5$$

- for sliding:

$$\mu = \tan \phi \Rightarrow \mu = .53$$

$$\phi = 28^\circ \quad C = 0$$

$$\gamma_w = 62.5 \text{ pcf.}$$

- RAPID DRAWDOWN CONDITION: This condition was modeled by treating 60% of the unbalanced fill as submerged and the remaining 40% as saturated.

DESIGN SECTIONS:

The design sections will be on separate plates accompanying this report.

27 Sept 49

CORPS OF ENGINEERS, U.S. ARMY

PAGE

3

SUBJECT

FORT FAIRFIELD - MAINE LPP

COMPUTATION

STOP LOG STRUCTURE / DOWNSTREAM

COMPUTED BY


ENestorides

CHECKED BY

DATE 2/6-87

I. STOP LOG Structure → Section I-I:

Not to Scale



Water level was determined by assuming 60% of unbalanced fill as submergence and remaining 40% saturated. Ground level is at 361.

| Item | COMPACTION | VERTICAL FORCES | Horizontal Forces | Moment arm | Moment |
|----------|--------------------------------|--------------------|-------------------|------------|---------------------|
| W_1 | $\frac{1}{2}(14.0)(2.0)(.15)$ | 2.10 | | 5.33 | 11.19 |
| W_2 | $(7.5)(1.0)(.15)$ | 1.13 | | 3.75 | 4.24 |
| W_3 | $(1.5)(14.0)(.15)$ | 3.15 | | 6.75 | 21.26 |
| W_4 | $(4.17)(35)(.15)$ | 21.89 | | 2.5 | 547.31 |
| W_5 | $(1.5)(14.0)(.15)$ | 3.15 | | 43.25 | 136.24 |
| W_6 | $(7.5)(1.0)(.15)$ | 1.13 | | 46.25 | 52.26 |
| W_7 | $\frac{1}{2}(14.0)(2.0)(.15)$ | 2.10 | | 44.67 | 93.80 |
| S_1 | $(11.0)(4.0)(.14)$ | 6.16 | | 2.0 | 12.32 |
| S_2 | $\frac{1}{2}(11.0)(1.57)(.14)$ | 1.21 | | 4.52 | 5.47 |
| S_3 | $(2.5)(35)(.12)$ | 10.5 | | 25.0 | 262.50 |
| S_4 | $\frac{1}{2}(12.0)(1.71)(.14)$ | 1.44 | | 45.43 | 65.42 |
| S_5 | $(4.0)(12.0)(.14)$ | 6.72 | | 48.0 | 322.56 |
| U_1 | $-10(.0625)(50)$ | -31.25 | | 25.0 | -781.25 |
| U_2 | $-\frac{1}{2}(.0625)(1)(50)$ | -1.56 | | 33.33 | -52.08 |
| P_{e1} | $\frac{1}{2}(.5)(.14)(2)^2$ | | .14 | 10.67 | 1.49 |
| P_{e2} | $(.5)(.14)(2)(10)$ | | 1.4 | 5.0 | 7.00 |
| P_{e3} | $\frac{1}{2}(.5)(.078)(10)^2$ | | 1.95 | 3.3 | 6.44 |
| P_{e4} | $-\frac{1}{2}(.5)(.14)(2)^2$ | | -.14 | 11.67 | -1.63 |
| P_{e5} | $-(.5)(.14)(2)(11)$ | | -1.54 | 5.5 | -8.47 |
| P_{e6} | $-\frac{1}{2}(.5)(.078)(11)^2$ | | -2.36 | 3.67 | -8.66 |
| P_{w1} | $\frac{1}{2}(.0625)(10)^2$ | | 3.13 | 3.3 | 10.33 |
| P_{w2} | $-\frac{1}{2}(.0625)(11)^2$ | | -3.78 | 3.67 | -13.87 |
| Σ | | $\Sigma V = 27.87$ | $\Sigma H = 7.20$ | | $\Sigma M = 693.87$ |

SUBJECT

FORT FAIRFIELD - MAINE LPP

COMPUTATION

STOP LOG STRUCTURE / DOWNSTREAM

COMPUTED BY

ENestorides

CHECKED BY

DATE 2-6-87

Stability at Toe et. 354:


- Overturning: $\frac{\Sigma M}{\Sigma V} = \frac{693.87}{27.87} = 24.9$ within mid $\frac{1}{3}$ 100% in bearing $> 75\%$ OK
- Sliding: $SF = \frac{\Sigma V \tan \phi + c}{\Sigma H} = \frac{27.87(.53)}{1.2} \Rightarrow 12.31 > 1.33$ OK
- Bearing: $f_{\pm} = \frac{\Sigma V}{\text{area}} \pm \frac{Mc}{I}$ $I = \frac{(1 \times 50)^3}{12} = 10,416.7$
 $f_{\pm} = \frac{27.82}{50} \pm \frac{27.82(0.1 \times 25)}{10,416.7} \Rightarrow .56 \pm .01 \Rightarrow f_{+} = .57 \text{ k/ft}^2$
 $f_{-} = .55 \text{ k/ft}^2$ } $< \frac{4 \text{ k}}{\text{ft}^2}$ OK

Stability \perp to the stop log centerline:Flood level $\Rightarrow 366.0$ Ground level behind stop logs $\Rightarrow 361$

5ft differential head.

Weight of structural wedge $\Rightarrow 27.87 \text{ k/ft} \times 8 \text{ ft wide}$
including uplift. 222.96 k  $P_w = \frac{1}{2}(.025)(5)^3 \Rightarrow 27.84 \text{ k}$ Sliding safety factor $\Rightarrow \frac{\Sigma V \tan \phi + c}{\Sigma H} \Rightarrow \frac{(222.96 \tan 28)}{27.34} = 4.34 > 1.33$ OK

Therefore, the U-channel structure satisfies criteria for overturning, sliding, and bearing pressure.

Stop-logs: The opening will be sand bagged around the rails and logs will start at el. 361.5 (top of rail). The 100 yr. event is 366.Logwall height required $= 366.0 - 361.5 \Rightarrow 4.5 \text{ feet} + 2 \text{ ft freeboard}$
6.5 ft of logs.Max. Pressure at bottom log: $6.5 \gamma_w \Rightarrow 406.25 \text{ lb/ft}^2$ Say timber is $10 \times 10 \Rightarrow 9 \frac{1}{2} \text{ dressed} \Rightarrow 406.25 \text{ lb/ft}^2 \times \frac{9.5}{12} = 321.61 \text{ lb/ft}$ $M_{\max} = \frac{wL^2}{8} = \frac{321.61(17.5)^2}{8} = 12,311.8 \text{ lb-ft}$ $S_{10 \times 10} = 142.896 \text{ in}^3$ $\sigma = \frac{M}{S} = \frac{12311.8(12)}{142.896} \Rightarrow 1033.91 \text{ lb/in}^2$ Ave. allowable bending stress (Oak, white, red) $\sim 1200 \text{ psi}$ OK

Use 2 bays of 9-10" x 10" timber logs 17.5 feet long.

SUBJECT

FORT FAIRFIELD - MAINE LPP

COMPUTATION

STOP LOG STRUCTURE / DOWNSTREAM


COMPUTED BY

ENestorides

CHECKED BY

DATE


2-6-87

Center Post:

A36 steel
 $f_b = .66 F_y = 23.76 \text{ ksi}$

$$\text{Max load} \Rightarrow (6.5)(17.5)(.0625 \text{ kcf}) = 7.11 \text{ k/ft}$$

Since the center post will be fixed at the base, it will act as a cantilever under a triangular load.



$$M_{\text{max}} = \frac{Wl}{3} = \frac{(23.11)(6.5)}{3} \Rightarrow 50.06 \text{ k.ft}$$

$$W = \frac{1}{2}(1.044)(6.5)^2$$

$$W = 23.11$$

$$V_{\text{shear max}} = W = 23.11 \text{ k}$$

$$S_{\text{req.}} = \frac{M_{\text{max}}}{f_{\text{bend}}} \Rightarrow \frac{50.06 \times 12 \text{ in}}{23.76} = 25.28 \text{ in}^3$$

$$\text{try } W12 \times 26 \quad S = 33.4 \text{ in}^3$$

$$W12 \times 22 \quad S = 25.4 \text{ in}^3$$

Since the W-section must fit the $9\frac{1}{2}$ " stop log, a W12 section is needed.

Use W12x26 (larger flange.)

$$\text{Deflection at free end } \delta = \frac{Wl^3}{15EI}$$

$$E = 29,000 \quad I = 204 \text{ in}^4$$

$$\delta = \frac{(23.11)(6.5 \times 12)^3}{15(29,000)(204)} \Rightarrow \delta_{\text{max}} = .123 \text{ in} \sim \frac{1}{8}''$$


Brace not required however anchorage is important.

Anchorage:

① Anchor bolts: Assume A325 bolts. Shear at base = 23.11 k

$$\text{try } 2 \text{ } \frac{7}{8}'' \phi \text{ anchor bolts} - f_r = \frac{23.11}{2(.601)} = 19.26 \text{ ksi}$$

$$\text{Area} = .601 \text{ in}^2$$



$$I = 2Ad^2$$

$$I = 2(.601)(6.2)^2$$

$$I = 45.39 \text{ in}^4$$

$$f_t = \frac{MC}{I} \Rightarrow \frac{(23.11)(2.17 \times 12)(.44)}{45.39} = 5.79 \text{ ksi}$$

$$\text{Allowables: } F_r = 21 \text{ ksi}$$

$$\text{for combined stress } F_t = 55 - 1.8f_r \leq 44$$

$$F_t = 55 - 1.8(19.26)$$


$$= 20.33 \leq 44$$

$$F_t = 20.33 \text{ ksi}$$

$$f_t \text{ actual} = 5.79 < 20.33 \quad \text{OK} \checkmark$$

$$f_r \text{ actual} = 19.26 < 21 \quad \text{OK} \checkmark$$

② No hardware: Fit W12x26 into a 7"x12" - 3 foot long depression



This should be adequate anchorage and the depression can be formed in the U-channel base slab.

27 Sept 49

CORPS OF ENGINEERS, U. S. ARMY

SUBJECT

FORT FAIRFIELD - MAINE LPP

PAGE

6

COMPUTATION

Gravity Walls / DOWNSTREAM


COMPUTED BY

ENestorides

CHECKED BY

DATE

2-7-87

II GRAVITY WALL - SECTION A-A:

| Item | COMPUTATION | Vertical forces | Horizontal forces | Moment arm | MOMENT |
|----------|---------------------------------|--------------------|-------------------|------------|-------------------|
| W_1 | $2(15)(.15)$ | 4.5 | | 1.0 | 4.5 |
| W_2 | $\frac{1}{2}(13.5)(9)(.15)$ | 9.11 | | 5.0 | 45.55 |
| S_1 | $(1.5)(9)(.14)$ | 1.89 | | 6.5 | 10.73 |
| S_2 | $\frac{1}{2}(13.5)(9)(.14)$ | 8.51 | | 8.0 | 68.08 |
| U_1 | $-7(.0625)11$ | -4.81 | | 5.5 | -26.46 |
| U_2 | $-\frac{1}{2}(.0625)(4.8)(11)$ | -1.65 | | 7.33 | -12.1 |
| P_{w1} | $\frac{1}{2}(.0625)(7)^2$ | | 1.53 | 2.33 | 3.57 |
| P_{w2} | $-\frac{1}{2}(.0625)(11.8)^2$ | | -4.35 | 3.93 | -17.11 |
| P_{e1} | $\frac{1}{2}(5)(.135)(7)^2$ | | 1.65 | 2.33 | 3.85 |
| P_{e2} | $-\frac{1}{2}(5)(.14)(3.2)^2$ | | -.36 | 12.87 | -4.63 |
| P_{e3} | $-(5)(.14)(3.2)(11.8)$ | | -2.64 | 5.9 | -15.58 |
| P_{e4} | $-\frac{1}{2}(5)(.078)(11.8)^2$ | | -2.72 | 3.93 | -10.70 |
| Σ | | $\Sigma V = 17.55$ | $\Sigma H = 6.89$ | | $\Sigma M = 49.7$ |

Stability at Toe

- Overturning: $\frac{\Sigma M}{\Sigma V} = \frac{49.7}{17.55} \Rightarrow 2.83$ % in bearing = $\frac{3(2.83)}{11} \times 100 \Rightarrow 77.2\% > 76$ OK ✓

- Sliding: $SF = \frac{\Sigma V \tan \phi + c}{\Sigma H} = \frac{(17.55) \tan 28^\circ + 0}{6.89} \Rightarrow 1.35 > 1.33$ OK ✓

- Bearing Pressure: $f_{max} = \frac{2\Sigma V}{3a} \Rightarrow \frac{2(17.55)}{3(2.83)} \Rightarrow 4.13$ $\frac{1}{4} \sim \frac{1}{4}$
Close enough for an extreme load condition.
OK ✓

27 Sept 49

CORPS OF ENGINEERS, U.S. ARMY

PAGE

7

SUBJECT

FORT FAIRFIELD - MAINE

LPP

COMPUTATION

Gravity Walls / Downstream

COMPUTED BY


ENestorides

CHECKED BY

DATE

2-7-87

III. GRAVITY WALL - SECTION B-B:



| Item | COMPUTATION | Vertical forces | Horizontal forces | Moment arm | Moment |
|-----------------|------------------------------------|-----------------|-------------------|------------|------------|
| W ₁ | 2(12)(.15) | 3.6 | | 1.0 | 3.6 |
| W ₂ | 1/2(10.5)(7)(.15) | 5.51 | | 4.33 | 23.86 |
| S ₁ | 1.6(7)(.14) | 1.57 | | 5.5 | 8.64 |
| S ₂ | 1/2(10.5)(7)(.14) | 5.15 | | 6.67 | 34.35 |
| U ₁ | - 7(9)(.0625) | - 3.94 | | 4.5 | - 17.73 |
| U ₂ | - 1/2(3.4)(9)(.0625) | - .96 | | 6.0 | - 5.76 |
| P _{w1} | 1/2(.0625)(7) ² | | 1.53 | 2.33 | 3.57 |
| P _{w2} | - 1/2(.0625)(10.4) ² | | - 3.38 | 3.47 | - 11.73 |
| P _{e1} | 1/2(.5)(.135)(7) ² | | 1.65 | 2.33 | 3.85 |
| P _{e2} | - 1/2(.5)(.14)(1.6) ² | | - .09 | 10.93 | - .98 |
| P _{e3} | - (.5)(.14)(1.6)(10.4) | | - 1.16 | 5.2 | - 6.03 |
| P _{e4} | - 1/2(.5)(.078)(10.4) ² | | - 2.11 | 3.47 | - 7.32 |
| Σ | — | ΣV = 10.93 | ΣH = -3.56 | — | ΣM = 28.32 |

Stability at Toe

- Overturning: $\frac{\Sigma M}{\Sigma V} = \frac{28.32}{10.93} = 2.59$ % in bearing = $\frac{3(2.59)}{9} \times 100\% = 86.4\% > 75\%$ OK ✓

- Sliding: $SF = \frac{\Sigma V \tan 28^\circ}{\Sigma H} = \frac{10.93(.53)}{3.56} \Rightarrow 1.63 > 1.33$ OK ✓

- Bearing: $f_{max} = \frac{2\Sigma V}{3a} \Rightarrow \frac{2(10.93)}{3(2.59)} \Rightarrow 2.81 \frac{k}{ft^2} < 4 \frac{k}{ft^2}$ OK ✓

27 Sept 49

CORPS OF ENGINEERS, U.S. ARMY

PAGE 8

SUBJECT

FORT FAIRFIELD - MAINE

LPP

COMPUTATION

STOP - LOG STRUCTURE / DOWNSTREAM

COMPUTED BY

ENestorides

CHECKED BY

DATE 2-18-87

LOGS:

Change to 27' opening } 13.5' per log

From previous calculations: Max pressure at bottom log $\Rightarrow 406.25 \text{ lb/ft}^2$ if timber is 8" x 8" $\approx 7\frac{1}{2}$ " dressed } $406.25 \times 7\frac{1}{2} = 253.91 \text{ lb/ft}$

$$M_{\max} = \frac{wL^2}{8} = \frac{(253.91)(13.5)^2}{8} = 5784.3 \text{ ft}\cdot\text{lb}$$

$$S_{8 \times 8} = 70.313 \text{ in}^3$$

$$\sigma = \frac{M}{S} = \frac{(5784.3)(12\frac{1}{4})}{70.313} = 987.18 \text{ psi}$$

allowable for white oak $\sim 1200 \text{ psi}$ OKTry 6" x 6" $\approx 5\frac{1}{2}$ " dressed $406.25 \times 5\frac{1}{2} \Rightarrow 186.20 \text{ lb/ft}$


$$M_{\max} = \frac{(186.20)(13.5)^2}{8} = 4241.82 \text{ ft}\cdot\text{lb}$$

$$S_{6 \times 6} = 27.729 \text{ in}^3$$

$$\sigma = \frac{M}{S} = \frac{4241.82 \times 12}{27.729} \Rightarrow 1835.69 \text{ psi}$$

NOT OKUSE 8" x 8" $\Rightarrow 2$ bays, each 13.5 ft long

Total: 22 logs required

Center Post:

$$\text{Max load} \Rightarrow 6.5(8w)(13.5) \Rightarrow 5.48 \text{ k/ft}$$

$$W = \frac{1}{2}(8w)(13.5)(6.5)$$

$$W = 17.82$$

$$M_{\max} = \frac{WL}{8} = \frac{17.82(6.5)}{8} = 38.62 \text{ k}\cdot\text{ft}$$

$$S_{\text{req}} = \frac{M_{\max}}{f_{\text{bend}}} = \frac{(38.62 \times 12\frac{1}{4})}{23.76} = 19.5 \text{ in}^3$$

$$f_b = 23.76 \text{ ksi}$$

$$= 0.66 F_y$$

$$\text{Use } W10 \times 22 \quad S_x = 23.2 \text{ in}^3$$

$$b_f = 5.75 \text{ in} \quad k_1 = \frac{1}{2}$$

$$\text{Length of bearing} = \frac{b_f}{2} - k_1 \Rightarrow 2.375 \text{ in} \quad \text{OK}$$

STOP GROOVE:

8" groove

Center Post anchorage:

3-ft deep depression

6" x 11"



27 Sept 49

CORPS OF ENGINEERS, U.S. ARMY

PAGE 9

SUBJECT

FORT FAIRFIELD - MAINE LPP

COMPUTATION

STOP LOG STRUCTURE - UPSTREAM

COMPUTED BY

ENestorides

CHECKED BY

DATE

2/5/87

FORT FAIRFIELD: STOP LOG STRUCTURE / UPSTREAM

The stop-log structure is a U-channel with one bay of stop-logs. The southern wall will abut against an existing concrete retaining wall while the north wall will retain the dike embankment. The north wall will also extend past the channel section to include concrete retaining walls on either end.

The structures were designed in accordance to the following Corps Criteria:

1. EC 1110-2-510 "Working Draft of the Retaining and Flood wall Manual 31 Aug. 1983 w/ revisions 15 July 1985"
2. ETZ 1110-2-256 "Sliding stability for Concrete structures" 24 June 1981.
3. EM 1110-2-2501 "Flood Wall Manual" Jan. 1948 w/changes.

LENGTH OF CHANNEL:

The use of sheet pile cutoff is discouraged due to the hardness of the foundation material. Therefore, a U-channel length was chosen [based on the differential head occurring during a flood] to minimize the possibility of seepage under the channel.

EM 1110-2-2501
Flood Wall Manual
Para. 108(c)

$$\text{Creep Ratio} \Rightarrow \frac{\text{Line of Creep}}{\Delta \text{Head}}$$


if ratio ≥ 4 (for sands, gravels no additional cutoff needed)

$$\Delta \text{Head} \Rightarrow (\text{Flood level}) - (\text{tail-ground level}) \Rightarrow (367.5 - 360.0) \Rightarrow 7.5 \text{ ft}$$

$$4 \times 7.5 = \text{min. line of creep} \Rightarrow 30.0 \quad \text{use a 16.0 ft long section.}$$

Frost depth 6 feet min.

The stop log structure and retaining walls are shown in plan below:



Each structure will be analysed separately in the pages to follow.

27 Sept 49

SUBJECT FORT FAIRFIELD - MAINE - LPP
 COMPUTATION STOP LOG STRUCTURE - UPSTREAM
 COMPUTED BY ENestorides CHECKED BY _____ DATE 2-5-87

DESIGN METHOD:

One section of the concrete U-channel and two typical sections of the retaining wall will be analyzed for stability under one load case: Load case R2 as described in the draft of the Retaining and Flood Wall Manual.

This load case represents a rapid drawdown situation which is an extreme loading for retaining structure. Since the area in question is in seismic zone One (minor damage) the earthquake condition is not critical.

All the structures are founded on compacted gravel fill or in certain areas, on the naturally deposited soils. Under Load Case R2, the structures must satisfy the following stability criteria:

- 75% of the base must be in compression,
- the factor of safety against sliding must be greater than 1.33,
- bearing pressures should not exceed the allowable k/ft^2 .

Design and Soil Parameters:

| | γ_{moist} | $\gamma_{saturated}$ | $\gamma_{submerged}$ | ϕ | c / δ |
|----------------------------|------------------|----------------------|----------------------|--------|--------------|
| Dumped Gravel bedding (RR) | .120 | .135 | .073 | 32° | 0/0° |
| Compacted Impervious | .135 | .140 | .078 | 30° | 0/0° |
| Foundation soil. | .130 | .137 | .075 | 28° | 0/0° |

- Consider Soil pressures using $K_0 \rightarrow$ at rest coefficient.

$$K_0 = 1 - \sin \phi \quad \phi = 30^\circ \quad \boxed{K_0 = .5}$$

- For Sliding: $\mu = \tan \phi \quad \phi = 28^\circ \quad \boxed{\mu = .53}$
 $c = 0 \text{ tsf}$


- RAPID DRAWDOWN: This condition was modeled by treating 60% of the unbalanced fill as submerged and the remaining 40% as saturated.

SUBJECT FORT FAIRFIELD - MAINE LPP

COMPUTATION STOP LOG STRUCTURE

COMPUTED BY E. Nestorides CHECKED BY _____ DATE 2-9-87

I. Stop Log U-Channel:



The water line behind the battered U-channel wall is at el. 366. This elevation was used to roughly represent 60% of the unbalanced fill on both sides of the wall. The contribution of the existing concrete wall on the U-channel will be modeled as the height of light fill it could retain.

| Item | Computation | Vertical Forces (k) | Horizontal forces (k) | Moment arm | Moment (K.FT) |
|----------------|---------------------------------|---------------------|-----------------------|------------|---------------|
| W ₁ | (1.5)(10.83)(.15) | 2.44 | | .75 | 1.83 |
| W ₂ | (4.17)(19.5)(.15) | 12.20 | | 9.75 | 118.92 |
| W ₃ | (1.5)(15)(.15) | 3.38 | | 20.25 | 68.45 |
| W ₄ | 1/2(15)(2.14)(.15) | 2.41 | | 21.71 | 52.32 |
| W ₅ | (1)(7.5)(.15) | 1.05 | | 23.25 | 24.41 |
| U | -12(.0625)(27) | -20.25 | | 13.50 | -273.38 |
| S ₁ | 2.5(18)(.12) | 5.40 | | 10.50 | 56.70 |
| S ₂ | 1/2(15)(2.14)(.14) | 2.25 | | 22.43 | 50.47 |
| S ₃ | (3.86)(15)(.14) | 8.11 | | 25.07 | 203.32 |
| Per | 1/2(.53)(.12)(15) ² | | 7.16 | 6.0 | 35.80 |
| Pe1 | -1/2(.5)(.14)(4) ² | | -.56 | 13.33 | -7.47 |
| Pe2 | -(.5)(.14)(4)(12) | | -3.36 | 6.0 | -20.16 |
| Pe3 | -1/2(.5)(.078)(12) ² | | -2.81 | 4.0 | -11.24 |
| Pw | -1/2(.0625)(12) ² | | -4.50 | 4.0 | -18.00 |
| Σ | — | ΣV = 16.99 | ΣH = -4.07 | — | ΣM = 281.97 |

Stability at toe:

- Overturning: $\frac{\Sigma M}{\Sigma V} = \frac{281.97}{16.99} = 16.60 \rightarrow \text{within kern } 100\% > 75\% \text{ in kern. OK}$

- Sliding: $SF = \frac{\Sigma V \tan \phi + c}{\Sigma H} = \frac{16.99(.53)}{4.07} = 2.21 > 1.33 \text{ OK}$

- Bearing Pressure: $f_{\pm} = \frac{16.99}{27.0} \pm \frac{(16.99)(3.1)(13.5)}{7640.25} = 16\% \text{ OK}$

$f_{\pm} = .63 \pm (.43) \Rightarrow \left. \begin{array}{l} f_{+} = .20 \text{ K/ft}^2 \\ f_{-} = 1.06 \text{ K/ft}^2 \end{array} \right\} < \frac{4 \text{ K}}{\text{ft}^2} \text{ OK}$

27 Sept 49

CORPS OF ENGINEERS, U.S. ARMY

PAGE 12

SUBJECT

FORT FAIRFIELD - MAINE LPP

COMPUTATION

STOP LOG STRUCTURE / UPSTREAM

COMPUTED BY

ENestorides

CHECKED BY

DATE

2-9-87

Stop LOGS:


Top of rail $\Rightarrow 361.5$
 Design flood $\Rightarrow 367.5$

$367.5 - 361.5 \Rightarrow 6.0 \text{ ft.} + 2 \text{ freeboard.}$
 $\Rightarrow 8.0$


 $7.5 \text{ Max. Pressure} \Rightarrow 8.0 (.0625) \Rightarrow .50 \text{ K/ft}^2$

Try $10" \times 10" \sim 9\frac{1}{2}"$ dressed $.50 \times \frac{9.5}{12} \Rightarrow .395 \text{ K/ft}$

Opening is $18'$ wide $\Rightarrow \text{max. Moment} = \frac{wl^2}{8} = \frac{(.395)(18)^2}{8} \Rightarrow 16.03 \text{ K.ft.}$

 $10" \times 10" S_{10 \times 10} = 142.896 \text{ in}^3$

$$\sigma = \frac{M}{S} = \frac{16.03 \times 12 \frac{1}{12}}{142.896} \Rightarrow \sigma = 1.35 \text{ K/in}^2$$


 $8" \times 12" S_{8 \times 12} = 165.313$

$$.50 \times \frac{7.5}{12} = .313 \quad M = \frac{(.313)(18)^2}{8} = 12.66 \text{ K.ft.}$$

$$\sigma = \frac{12.66(12)}{165.313} \Rightarrow .92 \text{ K/in}^2$$

$\sigma = \text{allowable (white, oak) } 1200 \text{ psi} \rightarrow \text{use } 8" \times 12" \text{ section.}$
 (12 required.)

Sliding of Structure due to Hydrostatic pressure: $\left. \begin{array}{l} \text{flood } 367.5 \\ \text{top of rail } \Rightarrow 360.0 \end{array} \right\} \Delta H = 7.5$



$$\frac{1}{2} .0625 (7.5)^2 \times 18 \Rightarrow 31.64 \text{ K}$$

Weight of structure $\Rightarrow 9.08 \text{ K/ft} \times 16 \text{ ft} \Rightarrow 145.28$
 including uplift.

$$\text{Sliding} \Rightarrow \frac{145.28(1.53)}{31.64} \Rightarrow 2.43 > 1.33 \quad \underline{\underline{OK}} \checkmark$$

27 Sept 49

CORPS OF ENGINEERS, U.S. ARMY

PAGE 13

SUBJECT

FORT FAIRFIELD MAINE - LPP

COMPUTATION

Stop Log Retaining wall /UPSTREAM


COMPUTED BY

ENestorides

CHECKED BY

DATE 2/10/87

II. TYPICAL RETAINING WALL:



| Item | COMPUTATIONS | VERTICAL forces | Horizontal forces | Moment arm | Moment ΣM |
|----------|----------------------------------|--------------------|----------------------|---------------|----------------------|
| W_1 | $2(16)(.15)$ | 4.8 | | 4.0 | 19.2 |
| W_2 | $\frac{1}{2}(16)(2.29)(.15)$ | 2.75 | | 5.76 | 15.84 |
| W_3 | $2(18)(.15)$ | 5.4 | | 9.0 | 48.6 |
| S_1 | $3(5)(.135)$ | 2.03 | | 1.5 | 3.05 |
| S_2 | $\frac{1}{2}(16)(2.29)(.14)$ | 2.56 | | 6.53 | 16.71 |
| S_3 | $10.71(16)(.14)$ | 23.99 | | 12.65 | 303.47 |
| U_1 | $-7(.0625)(18)$ | -7.88 | | 9.0 | -70.88 |
| U_2 | $-\frac{1}{2}(.0625)(6.6)(18)$ | -3.71 | | 12.0 | -44.55 |
| P_{e1} | $\frac{1}{2}(1.47)(.135)(7)^2$ | | .86 | 2.33 | 2.01 |
| P_{e2} | $-\frac{1}{2}(1.5)(.14)(4.4)^2$ | | -.68 | 15.07 | -10.21 |
| P_{e3} | $-(.5)(.14)(4.4)(13.6)$ | | -4.19 | 6.8 | -28.48 |
| P_{e4} | $-\frac{1}{2}(1.5)(.08)(13.6)^2$ | | -3.61 | 4.53 | -16.34 |
| P_{w1} | $\frac{1}{2}(.0625)(7)^2$ | | 1.53 | 2.33 | 3.57 |
| P_{w2} | $-\frac{1}{2}(.0625)(13.6)^2$ | | -5.78 | 4.53 | -26.18 |
| Σ | | $\Sigma V = 29.94$ | $\Sigma H = 11.87$ | | $\Sigma M = 215.84$ |

Stability at toe - 352

- Overturning:

$$\frac{\Sigma M}{\Sigma V} = \frac{215.81}{24.94} \Rightarrow 7.2 \text{ in mid } \frac{1}{3} \Rightarrow 100\% \text{ in bearing} \\ > 75\% \text{ OK}$$

- Sliding:

$$SF = \frac{E V \tan \phi}{\Sigma H} = 1.34 > 1.33 \quad \text{OK}$$

- Bearing Pressure:

$$f_t = \frac{EV}{\text{area}} \pm \frac{Mc}{I}$$


$$I = \frac{(V_R)^2}{12} \Rightarrow 486 \text{ fA}$$

$$f_{\pm} = \frac{29.94}{18} \pm \frac{29.94(1.8)(9)}{486} \Rightarrow 1.66 \pm .998$$

$$\left. \begin{aligned} f_1 &= 2.66 \text{ } 1/f_1^2 \\ f_2 &= 0.66 \text{ } 1/f_2^2 \end{aligned} \right\} < \frac{1}{f^2} \text{ OK}$$

27 Sept 49

CORPS OF ENGINEERS, U. S. ARMY

SUBJECT FORT FAIRFIELD - MAINE LPPPAGE 14COMPUTATION STOP LOG RETAINING WALL /UPSTREAMCOMPUTED BY E. Nestorides CHECKED BY _____ DATE 2-10-87**III.** Typical Section III: Retaining wall

| Item | COMPUTATIONS | Vertical forces | Horizontal forces | Moment arm | Moment (+) |
|-----------------|------------------------------------|--------------------|-------------------|------------|--------------------|
| W ₁ | 2(11.5)(.15) | 3.45 | | 3.5 | 12.08 |
| W ₂ | 1/2(11.5)(1.64)(.15) | 1.41 | | 5.05 | 7.12 |
| W ₃ | 2(12)(.15) | 3.6 | | 6.0 | 21.6 |
| S ₁ | (2.5)(5)(.135) | 1.69 | | 1.25 | 2.11 |
| S ₂ | 1/2(11.5)(1.64)(.14) | 1.32 | | 5.59 | 7.38 |
| S ₃ | (5.86)(11.5)(.14) | 9.43 | | 9.07 | 85.53 |
| U ₁ | - 7(12)(.0625) | - 5.25 | | 6.0 | - 31.5 |
| U ₂ | - 1/2(3.9)(12)(.0625) | - 1.46 | | 8.0 | - 11.68 |
| P _{w1} | 1/2(.0625)(7) ² | | 1.53 | 2.33 | 3.57 |
| P _{w2} | - 1/2(.0625)(10.9) ² | | - 3.71 | 3.63 | - 13.47 |
| P _{e1} | 1/2(1.47)(.075)(7) ² | | .86 | 2.33 | 2.00 |
| P _{e2} | - 1/2(.5)(.14)(2.6) ² | | - .24 | 11.77 | - 2.82 |
| P _{e3} | - (.5)(.14)(2.6)(10.9) | | - 1.98 | 5.45 | - 10.79 |
| P _{e4} | - 1/2(.5)(.078)(10.9) ² | | - 2.32 | 3.63 | - 8.42 |
| Σ | | $\Sigma V = 14.18$ | $\Sigma H = 5.86$ | | $\Sigma M = 62.71$ |

Stability at Toe el. 360.0

- Overtuning: $\frac{\Sigma M}{\Sigma V} = \frac{62.71}{14.18} = 4.42$ in mid. 1/3 \Rightarrow 100% bearing > 75% OK

- Sliding: $SF = \frac{14.18 \tan 28^\circ}{5.86} \Rightarrow 1.29 < 1.33$ close enough. OK

- Base Pressures: $f_{\pm} = \frac{14.18}{12} \pm \frac{(14.18)(1.58)(6)}{144} = 1.18 \pm .98$

$f_{+} = 2.11 \text{ k/ft}^2$
 $f_{-} = 1.25 \text{ k/ft}^2$
 $\left. \begin{array}{l} f_{+} = 2.11 \text{ k/ft}^2 \\ f_{-} = 1.25 \text{ k/ft}^2 \end{array} \right\} < \frac{4 \text{ k}}{\text{ft}^2} \text{ OK}$

27 Sept 49

SUBJECT

Fort Fairfield - Maine

COMPUTATION

Origination pipe head-wall

COMPUTED BY

J. Gagnon

CHECKED BY

DATE 2-13-87

DESIGN Method:

The headwall is designed and analyzed for stability as one unit. Criteria evolved from the Hydraulics appendix included:

1. Headwall soil elevation = 371
2. Side wall soil elevation \approx 370.0
(estimate from topography map)
3. Pipe invert elevation \approx 363.7 Min. (4' ϕ Pipe)

The load case used represents a rapid drawdown situation which is an extreme loading for a retaining structure of this sort. Since the seismic zone is one for this area, the earthquake condition is not critical.

The structure is designed for a foundation of compacted gravel fill. Under the rapid draw back load case, the structure must satisfy the following stability criteria:

1. 75% of the base must be in compression.
2. Factor of Safety Against sliding must exceed 1.33.
3. Bearing pressures should not exceed the allowable 4 K/ft²

Design and Soil Parameters:

| | γ_{sat} | γ_{sub} | ϕ | C |
|-----------------------|----------------|----------------|--------|---|
| Compacted gravel Fill | .145 | .0825 | 32° | 0 |

- Soil Pressures using $K_0 \approx$ at rest coefficient.

$$K_0 = 1 - \sin \phi \quad \phi = 32^\circ \quad K_0 = .47$$

- Sliding: $\mu = \tan \phi \quad \phi = 32^\circ \quad \mu = .62$
 $C = 0$

- Rapid Drawdown: This condition was modeled by using 40% of the unbalanced fill as submerged and the remaining as saturated. The 40% is representable as a drainable fill.

27 Sept 49

CORPS OF ENGINEERS, U.S. ARMY

PAGE 16

SUBJECT

Fort Fairfield - Maine

COMPUTATION

Drainage pipe headwall

COMPUTED BY

J. Guzman

CHECKED BY

DATE

2-13-87

The headwall is designed as both a retaining and outlet structure.

The structure is designed in accordance to the following Corps criteria:

1. EC 1110-2-510 "Working Draft of the Retaining and Flood wall Manual" 31 Aug. 1983, 7w/revisions 15 July 1985
2. ETL 1110-2-256 "sliding stability for concrete structures." 24 June 1981.



Soil and water pressures are developed from the following equations:

$$\text{Hydr. pressure} = \gamma_w h$$

$$\text{Saturated Soil Pressure} = \gamma_{\text{sat}}(h)(K_0)$$

$$\text{Submerged Soil Pressure} = \gamma_{\text{sub}}(h)(K_0)$$

SUBJECT _____
COMPUTATION _____
COMPUTED BY _____ CHECKED BY _____ DATE _____



SUBJECT

Fort Fairfield - Maine

COMPUTATION

Drain-pip headwall

COMPUTED BY

J. Gagnon

CHECKED BY

DATE

| ITEM | Computation | Vertical Forces (K) | Horizontal Forces (K) | Moment Arm (ft) | Moment @ TOE (K-ft) |
|-------------------------------------|--------------------------|---------------------|-----------------------|-----------------|---------------------|
| W ₁ | (1.5)(15)(10)(.15) | +33.75 | | 7.5 | +253.12 |
| W ₂ | (1.25)(10.5)(10)(.15) | +19.68 | | 15.625 | +307.5 |
| W ₃ | 1/2(2)(10.5)(10)(.15) | +15.75 | | 16.92 | +266.5 |
| W ₄ + W ₅ | 2(1.25)(13)(9)(.15) | +43.87 | | 8.5 | +372.89 |
| W ₅ + W ₆ | 2(2.83)(1.25)(9)(.15) | +9.55 | | 1.0 | +9.55 |
| W ₇ + W ₈ | 2(1/2)(2)(2)(.5)(.15) | +0.9 | | 0.667 | +0.60 |
| S ₁ | 1/2(1.81)(9.5)(10)(.145) | +12.47 | | 17.67 | +220.34 |
| U ₁ | (.094)(10)(18.25) | -17.15 | | 9.125 | -156.53 |
| U ₂ | (1/2)(.2)(10)(18.25) | -18.25 | | 12.167 | -220.05 |
| U ₃ + U ₄ | 1/2(2)(.094)(2)(2) | -.376 | | 1.0 | -.376 |
| U ₅ + U ₆ | 1/2(.175)(2)(2) | -.350 | | 1.33 | -.465 |
| Pw ₁ | 1/2(.294)(4.7)(10) | | -6.9 | 1.567 | -10.81 |
| Pw ₂ | 1/2(.094)(1.5)(10) | | +0.705 | 0.5 | +0.352 |
| Pw ₃ + Pw ₄ | 2(1/2)(.269)(4.3)(2) | | -2.31 | 1.43 | -3.30 |
| Pw ₅ + Pw ₆ | 2(1/2)(.094)(1.5)(2) | | +2.82 | 0.5 | +1.41 |
| PE ₁ | 1/2(.327)(4.8)(10) | | -7.85 | 6.3 | -49.44 |
| PE ₂ | (.327)(4.7)(10) | | -15.37 | 2.35 | -36.12 |
| PE ₃ | (1/2)(.182)(4.7)(10) | | -4.28 | 1.567 | -6.70 |
| PE ₄ | (1/2)(.058)(1.5)(10) | | +4.35 | 0.5 | +2.17 |
| PE ₅ + PE ₆ | 2(1/2)(.286)(4.2)(2) | | -2.40 | 5.7 | -13.69 |
| PE ₇ + PE ₈ | 2(4.3)(.286)(2) | | -4.92 | 2.15 | -10.57 |
| PE ₉ + PE ₁₀ | 2(1/2)(.167)(4.3)(2) | | -1.44 | 1.43 | -2.05 |
| PE ₁₁ + PE ₁₂ | 2(1/2)(.058)(1.5)(2) | | +1.74 | 0.5 | +0.87 |

$$\Sigma V = 99.84 \quad \Sigma H = 43.87$$

$$\Sigma M_{TOE} = 921.98$$

Stability @ TOE

$$\text{- Overturning: } \frac{\Sigma M}{\Sigma V} = \frac{921.98}{99.84} = 9.23 > \frac{18.25}{3} < 12.167 \text{ ok}$$

$$\text{- Sliding: } SF = \frac{\Sigma V \tan \phi + c}{\Sigma H} = \frac{(99.84)(.62)}{43.87} = 1.41 > 1.33 \text{ ok}$$

$$\text{- Bearing Pressure: } f = \pm \frac{99.84}{154.0} \pm \frac{99.84(.105)(9.125)}{5065}$$

$$(I = 5065)$$

$$f \pm = .65 \pm .019 \Rightarrow f + = .669 < 4.0 \text{ K/ft}^2 \text{ ok}$$

$$f - = .631$$

27 Sept 49

SUBJECT

FORT FAIRFIELD - MAINE LPP

COMPUTATION

PUMP STATION STABILITY

COMPUTED BY

ENestorides

CHECKED BY

DATE

2/11/87

FORT FAIRFIELD - PUMP STATION

The pumping station was checked for stability along the bottom foundation depth of 346.3, in the north/south direction.

The structure was analyzed in accordance to the following Corps Criteria:

1. EC 1110-2-510: "Working draft of the Retaining and Flood Wall Manual" 31 August 1983 (w/changes 15 July 85)
2. ETL 1110-2-256: "Sliding Stability of concrete structures." 24 June 1981.

The soil surrounding the pumping station is at el. 360. The "worst" case loading involved the soil saturated all around the pumping station. Since Fort Fairfield is in seismic zone One (minor damage), the earthquake load is not the critical loading.

The criteria for stability that must be satisfied are as follows:

- a) That, the factor of safety against sliding is greater than 1.5 (this is an assumed value found acceptable for the given building and load case)
- b) that the bearing pressures do not exceed the allowable 4 K/ft^2 ,
- c) and, that 100% of the base be in compression.

Attached are sections upon which the weight of the structure was calculated.

Soil Parameters: K_0 - at rest will be used for lateral soil pressures. The effects of the soil in the east/west direction resisting the overturning moment were not considered to be more conservative.
Assume: Compacted gravel fill around pumping station:

$$K_0 = 1 - \sin \phi = .43$$

$$\begin{aligned} \gamma_{\text{moist}} &= 135 \\ \gamma_{\text{sat}} &= 145 \\ \phi &= 35^\circ \end{aligned}$$

$$\text{Foundation Soil} \rightarrow \text{GEB} \Rightarrow \phi = 28^\circ \quad \mu = \tan \phi = .53$$

$$C = 0 \text{ tsf}$$

$$\text{allowable bearing capacity} = 4 \text{ K/ft}^2$$

27 Sept 49

NEW ENGLAND DIVISION

CORPS OF ENGINEERS, U.S. ARMY

PAGE 20

SUBJECT

FORT FAIRFIELD - MAINE LPP

COMPUTATION

PUMPING STATION STABILITY

COMPUTED BY


ENestorides

CHECKED BY

DATE 2-12-87

PUMPING STATION TYPICAL SECTION.

ELEVATION
NORTH / SOUTH



27 Sept 49

NEW ENGLAND DIVISION

CORPS OF ENGINEERS, U.S. ARMY

PAGE 21

SUBJECT

FORT FAIRFIELD - MAINE LPP

COMPUTATION


PUMPING STATION STABILITY

COMPUTED BY

ENestorides

CHECKED BY

DATE 2-12-87



27 Sept 49

CORPS OF ENGINEERS, U.S. ARMY

PAGE 22

SUBJECT

FORT FAIRFIELD - MAINE

COMPUTATION


PUMPING STATION STABILITY

COMPUTED BY

ENestorides

CHECKED BY


DATE 2/12-87



FOUNDATION PLAN

NOT TO ACCURATE SCALE

EQUIPMENT LAYOUT:



Pump \Rightarrow 3.0 k each
Engine \Rightarrow 3.3 k each
Gates \Rightarrow 1.3 k each (w/motor)
Oil Tank \Rightarrow 4 k

27 Sept 49

CORPS OF ENGINEERS, U.S. ARMY

PAGE 23

SUBJECT

FORT FAIRFIELD - MAINE LPP

COMPUTATION

Pumping Station Stability


COMPUTED BY

ENestorides

CHECKED BY


DATE 2-12-87

WEIGHT OF STRUCTURE AND CENTER OF GRAVITY



Concrete

| Item | COMPUTATION | WEIGHT (K) | \bar{y} Moment arm | M_x Moment about x-axis | \bar{x} moment arm | M_y Moment (K-F) arm |
|-----------------|---|-----------------------|----------------------|---------------------------|----------------------|------------------------|
| W ₁ | (1.33)(16.2)(25.33)(.15) | 81.86 | 22.84 | 1869.77 | 12.67 | 1037.22 |
| W ₂ | (1.17)(9.1)(22.67)(.15) | 36.21 | 21.59 | 781.67 | 12.67 | 458.72 |
| W ₃ | (3.17)(3.5)(22.67)(.15) | 37.73 | 19.42 | 732.69 | 12.67 | 478.02 |
| W ₄ | (11.17)(1.5)(22.67)(.15) | 56.98 | 12.25 | 697.95 | 12.67 | 721.94 |
| W ₅ | (1.33)(15.95)(25.33)(.15) | 80.60 | 6.0 | 483.60 | 12.67 | 1021.21 |
| W ₆ | (4.0)(1.33)(28)(.15) | 22.84 | 3.33 | 74.41 | 15.33 | 342.53 |
| W ₇ | (1.33)(15.45)(30.66)(.15) | 94.50 | .67 | 63.32 | 15.33 | 1448.72 |
| W ₈ | (4.0)($\frac{3}{2}$)(28)(.15) | 7.06 | 3.33 | 23.50 | 15.33 | 108.17 |
| W ₉ | (5.5)($\frac{3}{2}$)(22.67)(.15) - 2(3.33)(3.67)(.15) | 28.44 | 14.42 | 410.16 | 12.67 | 360.39 |
| W ₁₀ | (5.83)(.42)(23.0)(.15) - (5)(11)(.15)(.42) | 19.47 | 14.59 | 284.11 | 12.50 | 243.41 |
| W ₁₁ | (1.33)(14.2)(15.5)(.15) | 43.91 | 14.42 | 633.18 | .67 | 29.42 |
| W ₁₂ | (1.33)(15.95)(15.5)(.15) | 49.32 | 14.42 | 711.21 | 24.66 | 1216.27 |
| W ₁₃ | (1.33)(15.45)(22.17)(.15) | 68.33 | 12.42 | 848.71 | 29.99 | 2049.34 |
| W ₁₄ | (4.0)(15.45)(1.33)(.15) | 12.33 | 3.33 | 41.06 | .67 | 8.26 |
| W ₁₅ | (1.0)(1.42)(25.33)(.15) | 5.40 | 6.17 | 33.29 | 12.67 | 68.36 |
| W ₁₆ | (1.0)(1.42)(25.33)(.15) | 5.40 | 23.0 | 124.09 | 12.67 | 68.36 |
| W ₁₇ | (1.42)(1.0)(15.5)(.15) | 3.30 | 14.42 | 47.61 | 24.33 | 80.33 |
| W ₁₈ | (1.42)(1.0)(15.5)(.15) | 3.30 | 14.42 | 47.61 | .67 | 2.21 |
| W ₁₉ | (4.0)(.42)(18.19)(.15) | 4.58 | 14.42 | 66.10 | 27.33 | 125.28 |
| W ₂₀ | (4.0)(1.33)(18.19)(.15) | 14.52 | 14.42 | 209.32 | 27.33 | 396.91 |
| CMU1 | (12)(1)(25.33)(.08) | 24.32 | 22.84 | 555.40 | 12.67 | 308.09 |
| CMU2 | (12)(1)(25.33)(.08) | 24.32 | 5.84 | 142.01 | 12.67 | 308.09 |
| CMU3 | (12)(1)(15.5) - (1)(7)(10)(.08) | 9.28 | 14.42 | 133.82 | .67 | 6.22 |
| CMU4 | (12)(1)(15.5)(.08) | 14.88 | 14.42 | 214.57 | 24.66 | 366.94 |
| Σ | | W _T 748.98 | — | ΣM_x 9229.16 | — | ΣM_y 1254.21 |



$$\bar{x} = \frac{\Sigma M_y}{W_T} = \frac{1254.21}{748.98}$$

$$\bar{x} = 15.04 \text{ ft}$$

$$\bar{y} = \frac{\Sigma M_x}{W_T} = \frac{9229.16}{748.98}$$

$$\bar{y} = 12.33 \text{ ft}$$

$$I_x \rightarrow \frac{(30.66)(23.5)^3}{12} = 33158 \text{ ft}^4$$

$$I_y = \frac{(23.5)(30.66)^3}{12} = 56442 \text{ ft}^4$$


$$\text{Area} \rightarrow (23.5)(30.66) = 720.51$$

27 Sept 49

SUBJECT FORT FAIRFIELD - MAINE LPP


COMPUTATION PUMPING STATION STABILITY

COMPUTED BY ENestorides CHECKED BY DATE 2-12-87



LOAD CASE 1: Flood conditions,
surrounding backfill submerge
water in sump chamber.

1. UPLIFT:



Uplift felt on base slab.

$$A u_1 \Rightarrow 136.08$$

$$\uparrow U_1 = (136.08)(14.7)(.0625) = 125.02 \text{ K}$$

$$A u_2 \Rightarrow 268.08$$

$$\uparrow U_2 = (268.08)(12.7)(.0625) = 212.79 \text{ K}$$

$$A u_3 \Rightarrow 316.35$$


$$\uparrow U_3 \Rightarrow (316.35)(14.45)(.0625) = 285.79 \text{ K}$$

$$\uparrow U_{31} = 184.42 \text{ K}$$

$$\uparrow U_{32} = 101.29 \text{ K}$$

- HORIZONTAL HYDROSTATIC FORCES CANCEL OUT.

2. SOIL PRESSURES:



$P_{u1} = P_{s1}$ and Cancel out

$$P_s = k_o (1.69)(14.7)$$

$$\Rightarrow 4.33 \text{ K/ft Linear}$$

$$\text{Resultant } P_s \Rightarrow 4.33 \text{ K/ft} \times 30.66 = 132.91 \text{ K}$$

at 7.35 ft above toe

3. WATER IN SUMP CHAMBER:

Area of sump chamber: $(5.5 \text{ ft})(22.67) = 351.39 \text{ ft}^2$
 water at el. 357. $(357 - 348.8) \Rightarrow 8.2 \text{ ft of water}$

Volume of water in sump chamber $\Rightarrow 2881.40 \text{ ft}^3$

$$W_{w1} = (.0625)(2881.40) \Rightarrow 180.09 \text{ K at } 14.42 \text{ ft from toe.}$$

3' of water in By-pass Channel: $V_{o1} \Rightarrow 4(28)(3) \Rightarrow 336 \text{ ft}^3$

$$W_{w2} = (336 \text{ ft}^3)(.0625 \text{ K/ft}^3) = 21 \text{ K}$$

at 3.33 ft from toe

$$V_{o2} = 4(18.19)(3) \Rightarrow 218.28$$

$$W_{w3} = (218.3)(.0625) = 13.64 \text{ K at } 14.41 \text{ ft from toe}$$

27 Sept 49

SUBJECT

FORT FAIRFIELD - MAINE LPP

COMPUTATION

PUMPING STATION STABILITY

COMPUTED BY

ENestorides

CHECKED BY

DATE

2-12-87

Stability Analysis [with equipment as shown in layout on previous pages, no other extras (doors, ladders, hatch etc.)]

| Item | VALUE (K) | Moment arm ft | Moment (K.ft) |
|-----------------|--|---------------|----------------------|
| W ₅ | 748.38 | 12.33 | 9227.53 |
| W _{w1} | 180.09 | 14.42 | 2596.90 |
| W _{w2} | 21 | 3.33 | 69.93 |
| W _{w3} | 13.64 | 14.41 | 196.55 |
| U ₁ | - 125.02 | 21.67 | - 2709.18 |
| U ₂ | - 212.79 | 12.25 | - 2606.68 |
| U _{g1} | - 184.42 | 3.33 | - 614.12 |
| U _{g2} | - 101.29 | 15.08 | - 1527.45 |
| *P ₃ | - 132.91 | 7.35 | - 976.89 |
| Pump 1 | 3.0 K | 17.0 | 51.0 |
| Pump 2 | 3.0 K | 17.0 | 51.0 |
| Eng 1 | 3.3 K | 11.75 | 38.78 |
| Eng 2 | 3.3 K | 11.75 | 38.78 |
| Gate 1 | 1.3 | 4.5 | 5.85 |
| Gate 2 | 1.3 K | 4.5 | 5.85 |
| oil tank | 4.0 K | 2.5 | 10.0 |
| Σ | $\Sigma V = 358.79$ $\Sigma H = 132.91$ | | $\Sigma M = 3857.62$ |

Stability at Toe el. 345.3

$$\text{Overturning: } \frac{\Sigma M}{\Sigma V} = \frac{3857.62}{358.79}$$

$$\Rightarrow 10.75 \text{ ft.}$$

$$7.8 < \text{Mid } \frac{1}{3} < 15.7 \left. \begin{array}{l} \text{OK} \\ \text{within Mid } \frac{1}{3} \\ \text{100\% in bearing} \end{array} \right\}$$

Sliding:

$$SF = \frac{\Sigma V \tan \phi + c}{\Sigma H} = \frac{358.79 (\tan 28^\circ) + 132.91}{132.91}$$

$$SF = 1.44 < 1.5 \quad \text{OK}$$

This is a bit low however given that the effects of the soil press. resisting sliding in the East/West direction were not considered, the above factor is found acceptable.


* Horizontal force.

$$\text{Bearing Pressure: } f_{\pm} = \frac{\Sigma V}{\text{area}} \pm \frac{M \times c_y}{I_x} \quad (\text{N/s direction})$$

$$I_x = 33158 \text{ ft}^4 \quad c_y = 11.75 \text{ ft} \quad \text{Area} = 720.51$$

$$f_{\pm} \Rightarrow \frac{358.79}{720.51} \pm \frac{358.79 (11.75)}{33158} \Rightarrow .498 \pm .127$$

$$\left. \begin{array}{l} \text{along (A-A)} \quad f_{+} = .63 \text{ K/ft}^2 \\ \text{along (B-B)} \quad f_{-} = .37 \text{ K/ft}^2 \end{array} \right\} < 4 \text{ K/ft}^2 \quad \text{OK.}$$



The following tables provide a detailed breakdown of the quantities and costs of the selected plan. Costs are based on January 1987 prices.

AROOSTOOK RIVER, FORT FAIRFIELD, MAINE

SELECTED FLOOD PROTECTION DIKE PLAN

=====

| ITEM | QUANTITY | UNITS | UNIT PRICE | TOTAL COST |
|-----------------------------|----------|-------|-------------|-------------|
| ---- | ----- | ----- | ----- | ----- |
| DIKE SECTION | 1 | JOB | \$1,900,000 | \$1,900,000 |
| PRESSURE CONDUIT | 1 | JOB | \$180,000 | \$180,000 |
| PUMPING STATION | 1 | JOB | \$460,000 | \$460,000 |
| STOP-LOGS & RETAINING WALLS | 1 | JOB | \$315,000 | \$315,000 |
| STORM DRIANAGE SYSTEM | 1 | JOB | \$165,000 | \$165,000 |
| SEWER RELOCATION | 1 | JOB | \$275,000 | \$275,000 |
| TOTAL CONSTRUCTION COST | | | | \$3,295,000 |

DIKE SECTION

=====

| ITEM | QUANTITY | UNITS | UNIT PRICE | TOTAL COST |
|---------------------------------------|----------|-------|------------|-------------|
| ---- | ----- | ----- | ----- | ----- |
| SITE PREPARATION | 1 | JOB | \$25,000 | \$25,000 |
| EXCAVATION | 22320 | CY | \$6 | \$134,000 |
| STONE PROTECTION | 11870 | CY | \$35 | \$415,000 |
| GRAVEL BEDDING | 4020 | CY | \$15 | \$60,000 |
| ROAD GRAVEL | 1550 | CY | \$12 | \$19,000 |
| DUMPED GRAVEL FILL | 16890 | CY | \$10 | \$169,000 |
| COMPACTED IMPERV. FILL | 65510 | CY | \$7 | \$459,000 |
| COMPACTED GARVEL FILL | 13680 | CY | \$12 | \$164,000 |
| UNDERDRIAN - 6"BCCM | 1400 | LF | \$6 | \$8,000 |
| UNDERDRIAN - 12"BCCM | 1200 | LF | \$12 | \$14,000 |
| FILTER MATERIAL - STONE | 1740 | CY | \$30 | \$52,000 |
| OBSERVATION RISERS | 12 | EA | \$300 | \$4,000 |
| TOPSOIL SEEDED | 9500 | SY | \$3 | \$29,000 |
| COMPACTED RANDOM FILL | 4000 | CY | \$4 | \$16,000 |
| SUBTOTAL | | | | \$1,568,000 |
| TOTAL COST INCLUDING 20 % CONTINGENCY | | | | \$1,900,000 |

PRESSURE CONDUIT

=====

| ITEM | QUANTITY | UNITS | UNIT PRICE | TOTAL COST |
|---------------------------------------|----------|-------|------------|------------|
| ---- | ----- | ----- | ----- | ----- |
| EXCAVATION | 2000 | CY | \$6 | \$12,000 |
| DRAGBOX | 1 | ITEM | \$4,500 | \$5,000 |
| CONCRETE STRUCTURAL | 45 | CY | \$300 | \$14,000 |
| SLIDE GATE W/FLAP GATE | 1 | ITEM | \$20,000 | \$20,000 |
| STONE BEDDING | 110 | CY | \$30 | \$3,000 |
| SAND BEDDING | 400 | CY | \$15 | \$6,000 |
| BACKFILL (EXCAVATED MATL) | 1400 | CY | \$4 | \$6,000 |
| PAVEMENT SYSTEM | 700 | SY | \$13 | \$9,000 |
| 48" RCP | 350 | LF | \$80 | \$28,000 |
| MANHOLE (6' ID 16' DEEP) | 1 | EA | \$4,000 | \$4,000 |
| INLET & OUTLET STRUCTURES | 2 | JOB | \$10,000 | \$20,000 |
| MANHOLE INLETS | 2 | EA | \$150 | \$300 |
| STEPS | 12 | EA | \$15 | \$180 |
| 48"DUTILE IORN PIPE | 125 | LF | \$200 | \$25,000 |
| SUBTOTAL | | | | \$152,480 |
| TOTAL COST INCLUDING 20 % CONTINGENCY | | | | \$180,000 |

PUMPING STATION

=====

| ITEM | QUANTITY | UNITS | UNIT PRICE | TOTAL COST |
|---------------------------------------|----------|-------|------------|------------|
| ---- | ----- | ----- | ----- | ----- |
| PUMPS ENGINES & GEAR UNITS | 1 | ITEM | \$123,300 | \$123,000 |
| DISCHARGE PIPE | 1 | ITEM | \$52,300 | \$52,000 |
| STATION SLUICE GATES | 1 | ITEM | \$39,500 | \$40,000 |
| HEATING | 1 | ITEM | \$2,000 | \$2,000 |
| FUEL TANK & PIPING | 1 | ITEM | \$3,100 | \$3,000 |
| LEVEL GAGES | 1 | ITEM | \$5,400 | \$5,000 |
| VENTILATION | 1 | ITEM | \$2,000 | \$2,000 |
| EMERGENCY GEN. | 1 | ITEM | \$10,000 | \$10,000 |
| CONC. WELL STRUCTURAL | 45 | CY | \$300 | \$14,000 |
| SLUICE GATE (48" GRAVITY P) | 1 | ITEM | \$20,000 | \$20,000 |
| PUMPING STATION - R. CONC. | 180 | CY | \$300 | \$54,000 |
| - 8" CUM WALL | 1010 | SF | \$5 | \$5,000 |
| - 8" BRICK WALL FACE | 1260 | SF | \$6 | \$8,000 |
| ROADWAY GURD POSTS | 1 | JOB | \$3,000 | \$3,000 |
| CHAIN LINK FENCING | 1 | JOB | \$3,000 | \$3,000 |
| 6'X10' DOOR | 1 | EA | \$1,500 | \$2,000 |
| 48" DUCTILE IORN PIPE | 140 | LF | \$200 | \$28,000 |
| STONE BEDDING | 150 | CY | \$30 | \$5,000 |
| SAND BEDDING | 150 | CY | \$15 | \$2,000 |
| STEEL SHEET PILING | 180 | SF | \$20 | \$4,000 |
| EXCAVATION | 350 | CY | \$4 | \$1,000 |
| SUBTOTAL | | | | \$386,000 |
| TOTAL COST INCLUDING 20 % CONTINGENCY | | | | \$460,000 |

STOP-LOGS & RETAINING WALLS

=====

| ITEM | QUANTITY | UNITS | UNIT PRICE | TOTAL COST |
|---------------------------------------|----------|-------|------------|------------|
| ---- | ----- | ----- | ----- | ----- |
| EXCAVATION | 1260 | CY | \$6 | \$8,000 |
| T-WALL | 135 | CY | \$300 | \$41,000 |
| STOP-LOG (UPSTREAM) | 108 | CY | \$300 | \$32,000 |
| 8"X10" WHITE OAK LOGS 18.5' | 12 | EA | \$250 | \$3,000 |
| SAND BAGS | 135 | EA | \$10 | \$1,000 |
| 100' SINGLE RR TRACK | | | | |
| REMOVE & RESTOR | 1 | JOB | \$10,000 | \$10,000 |
| COMPACTED GRAVEL | 340 | CY | \$12 | \$4,000 |
| GRAVITY WALL | 320 | CY | \$300 | \$96,000 |
| STOP-LOG (DOWNSTREAM) | 65 | CY | \$300 | \$20,000 |
| 8"X8" WHITE OAK LOGS 14' | 22 | EA | \$150 | \$3,000 |
| W10X22 STL CENTER POST 11' | 1 | EA | \$500 | \$1,000 |
| 120' DOUBLE RR TRACK | | | | |
| REMOVE & RESTOR | 1 | JOB | \$25,000 | \$25,000 |
| REPLACE RR SWITCH | 1 | JOB | \$20,000 | \$20,000 |
| SUBTOTAL | | | | \$264,000 |
| TOTAL COST INCLUDING 20 % CONTINGENCY | | | | \$315,000 |

STORM DRAINAGE SYSTEM



=====

| ITEM | QUANTITY | UNITS | UNIT PRICE | TOTAL COST |
|---------------------------------------|----------|-------|------------|------------|
| ---- | ----- | ----- | ----- | ----- |
| EXCAVATION | 3600 | CY | \$6 | \$22,000 |
| STONE BEDDING | 220 | CY | \$30 | \$7,000 |
| SAND BEDDING | 650 | CY | \$15 | \$10,000 |
| BACKFILL (EXCAVATED MATL) | 2700 | CY | \$4 | \$11,000 |
| 30" ID RCP | 420 | LF | \$40 | \$17,000 |
| 24" ID RCP | 330 | LF | \$24 | \$8,000 |
| 18" ID RCP | 830 | LF | \$18 | \$15,000 |
| 12" ID RCP | 780 | LF | \$10 | \$8,000 |
| MANHOLES 4' ID 8' DEEP | 15 | EA | \$1,500 | \$23,000 |
| CATCH BASINS & FRAMS | 15 | EA | \$500 | \$8,000 |
| MANHOLE INLETS | 30 | EA | \$150 | \$5,000 |
| TIE IN EXIST 12" DRAIN | 2 | JOB | \$250 | \$1,000 |
| TOPSOIL SEEDED | 2200 | SY | \$3 | \$7,000 |
| SUBTOTAL | | | | \$142,000 |
| TOTAL COST INCLUDING 20 % CONTINGENCY | | | | \$165,000 |

SEWER RELOCATION

=====

| ITEM | QUANTITY | UNITS | UNIT PRICE | TOTAL COST |
|---------------------------------------|----------|-------|------------|------------|
| ---- | ----- | ----- | ----- | ----- |
| EXCAVATION | 4000 | CY | \$6 | \$24,000 |
| SAND BEDDING | 400 | CY | \$15 | \$6,000 |
| STONE BEDDING | 150 | CY | \$30 | \$5,000 |
| BACKFILL (EXCAVATED MATL) | 3600 | CY | \$4 | \$14,000 |
| DRAGBOX (TRENCH CONST) | 1 | ITEM | \$4,500 | \$5,000 |
| 5' ID MANHOLE (13'DEEP) | 8 | EA | \$3,500 | \$28,000 |
| 18" RCP | 1400 | LF | \$18 | \$25,000 |
| TIE IN EXIST SEWERS | 17 | EA | \$250 | \$4,000 |
| ABONDON EXIST 16" PLUG | 21 | EA | \$50 | \$1,000 |
| BACKFILL MANHOLES | 9 | EA | \$100 | \$1,000 |
| TOPSOIL SEEDED | 2200 | SY | \$3 | \$7,000 |
| PERMANENT SHEETING NEAR RR | 4500 | SF | \$25 | \$113,000 |
| SUBTOTAL | | | | \$233,000 |
| TOTAL COST INCLUDING 20 % CONTINGENCY | | | | \$275,000 |





DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION
CORPS OF ENGINEERS
WALTHAM, MASS.

ST. JOHN RIVER BASIN
LOCAL PROTECTION PROJECT
AROOSTOOK RIVER
FORT FAIRFIELD, MAINE
PLAN AND PROFILE OF STORMDRAIN

SCALE: AS SHOWN

DATE: MAR. 1987

PLATE C-1




DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION
CORPS OF ENGINEERS
WALTHAM, MASS.


ST. JOHN RIVER BASIN
LOCAL PROTECTION PROJECT
AROOSTOOK RIVER
FORT FAIRFIELD, MAINE
PLAN AND PROFILE OF STORMDRAIN


SCALE: AS SHOWN

DATE: MAR. 1987

PLATE C-1








OPERATING FLOOR PLAN

















SCALE: $\frac{3}{8}'' = 1' - 0''$








SUMP PLAN

SCALE: $\frac{3}{8}'' = 1' - 0''$.

| PANEL | | | | |
|--|-------------------|-----------------|---------------------------------|--------------------|
| 120/240V, 11, 3 WIRE, 100AMP. MAIN BREAKER | | | | |
| CIRCUIT NUMBER | BREAKER SIZE AMPS | NUMBER OF POLES | SERVES | CONNECTED LOAD KVA |
| 1 | 20 | 1 | Lighting | 1.2 |
| 2 | 20 | 1 | Spare | - |
| 3 | 20 | 1 | Furnace | 2 @ 1/3 |
| 4 | 20 | 1 | Receptacles | 1.0 |
| 5 | 20 | 1 | Sump lighting | 0.8 |
| 6 | 20 | 1 | Float well receptacle | 0.2 |
| 7 | 20 | 2 | Spare | 1 |
| 8 | 20 | 1 | Sump exhaust fan | 1/3 |
| 9 | 20 | 1 | Spare | - |
| 10 | 20 | 1 | Spare | - |
| 11 | 20 | 1 | Grease unit | 1/3 |
| 12 | 20 | 1 | Exterior lighting | 0.6 |
| 13 | 20 | 2 | Sump pump | 1 |
| 14 | 20 | 2 | Floor stand No. 1 | 1 |
| 15 | 20 | 2 | Floor stand No. 2 | 1 |
| 16 | 20 | 2 | Sluice gate (Gravity Outlet) | 2 |

| LEGEND | |
|---|---|
| SYMBOL | DESCRIPTION |
|  | Ceiling outlet |
|  | Wall outlet |
|  | Junction box |
|  | Duplex convenience outlet - WP indicates weatherproof |
|  | Motor - HP as indicated |
|  | Emergency lighting unit |
|  | Panel |
|  | Controller |
|  | Telephone outlet, 1'-0" up |
|  | Branch circuit concealed in ceiling or wall |
|  | Branch circuit in floor |
|  | Home run to panelboard. Note: Any circuit without further designation indicates a two-wire circuit. For a greater number of wires indicate as follows  (3 wires)  (4 wires) etc. |
|  | Single pole switch, 4'-0" up |
|  | Floor switch |

[illegible]



DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION
CORPS OF ENGINEERS
WALTHAM, MASS.

**ST. JOHN RIVER BASIN
LOCAL PROTECTION PROJECT**

AROOSTOOK RIVER
FORT FAIRFIELD, MAINE

PUMPING STATION

MECHANICAL - PLANS AND SECTION

SCALE: AS SHOWN

DATE: MAR. 1987

SECTION D

SOCIAL AND ECONOMIC ANALYSIS

FORT FAIRFIELD, ME
ECONOMIC ANALYSIS

| <u>Table of Contents</u> | <u>Page No.</u> |
|---|-----------------|
| Introduction | 1 |
| Socio-Economic Setting | 1 |
| Study Area | 2 |
| Valuation of Properties in the Study Area | 3 |
| Flood Damage Surveys | 3 |
| Recent and Planned Improvements in Study Area | 4 |
| Susceptibility to Flooding | 4 |
| Recurring Losses | 5 |
| Annual Losses | 5 |
| Economic Benefit Analysis | 6 |
| Inundation Reduction Benefit | 6 |
| Improvement Plans Evaluated | 7 |
| Benefit Estimation | 7 |
| Reduced Pumping Costs | 7 |
| Reduction in Flood Insurance Overhead Costs | 8 |
| Summary of Benefits | 8 |
| Economic Justification | 9 |

Introduction

The purpose of this section is to measure the beneficial contributions to national economic development that are associated with the water resources improvement plans for the Fort Fairfield floodplain. The extent to which the flood control needs of the area are met by the plans will be determined by estimating the dollar value of inundation reduction benefits produced by the plans. Explanatory rationale and supporting documentation will be presented. The measure of each plan's economic justification is the benefit-cost ratio, which is calculated by dividing the dollar value of the total annual benefits to be realized over the plan's economic life by the annual charges for the plan's total cost. A benefit-cost ratio of 1.0 or greater is necessary for Federal participation in water resources improvement projects. Simply, one dollar's worth or more of flood reduction benefits is required for each dollar to be expended on project construction. If more than one plan of improvement has a benefit-cost ratio greater than 1.0 then the plan with the greatest amount of net benefits (ie. total annual benefits minus total annual costs) is chosen. The plan which maximizes net benefits allocates limited resources in the most efficient manner and provides the greatest return on public investment. The analysis contained in this section was performed in accordance with Economic Environmental Principles and Guidelines for Water and Related Land Resources Implementation Studies, Water Resources Council, 1983. Dollar values stated in this section reflect the December 1986 price level. Discounting and amortization was performed at 8-7/8 percent, the current interest rate for Federal water resources improvement project evaluation.

Socio-Economic Setting

The town of Fort Fairfield is located in Aroostook County, Maine. This county contains more than 20 percent of Maine's land area but only 8 percent of its people. The rural nature of the county is indicated by its population density per square mile of 13.6 compared to 35.3 statewide. The population of Fort Fairfield is 4,376 (1980 U.S. Census). Both the town and Aroostook County have experienced population declines over the past 20 years, while the state of Maine population overall has been growing since 1940.

TABLE 1
POPULATION TRENDS 1960 - 1980

| | <u>1960</u> | <u>1970</u> | <u>1980</u> | <u>% Change 1960-1970</u> | <u>% Change 1970-1980</u> |
|------------------|-------------|-------------|-------------|-------------------------------|-------------------------------|
| Fort Fairfield | 5,876 | 4,859 | 4,376 | -17.3 | -9.9 |
| Aroostook County | 106,064 | 94,078 | 91,331 | -11.3 | -2.9 |
| State of Maine | 969,300 | 993,700 | 1,124,660 | +2.5 | +13.2 |

The population declines in Fort Fairfield and Aroostook County can be traced to fewer agricultural jobs due to mechanization and a decline in competitive market position in the potato industry. Other employment sectors are also not providing job opportunities in sufficient numbers to halt emigration of job-seekers from the county. The increases in population for the state of Maine reflect the growth and development in the southern counties, especially the seacoast communities and those nearby.

The economic well-being of Fort Fairfield inhabitants can be measured by examining per capita income, median family income and percentage of families at or below the poverty level.

TABLE 2
INDICATORS OF ECONOMIC WELL-BEING

| | <u>Per Capita Income</u> | <u>Median Family Income</u> | <u>% of Families below Poverty Level</u> |
|------------------|------------------------------|---------------------------------|--|
| Fort Fairfield | \$4,460 | \$14,022 | 10.2% |
| Aroostook County | \$4,826 | \$13,924 | 13.3% |
| State of Maine | \$5,768 | \$16,167 | 9.8% |

Fort Fairfield and Aroostook County obviously have income measures below statewide figures because of their rural nature and lack of a strong industrial base. However, Fort Fairfield families do fare slightly better than average county families in terms of median income. Also, while the town's poverty level percentage is nearly that of the state it is 3 percentage points lower than that of Aroostook County.

According to the 1980 U.S. Census, the Fort Fairfield labor force was 1,735 people of which 1,598 were employed. Of the employing industries, services accounted for the largest share (23%) mostly in health and education. Other major employing industries are: manufacturing (17.5%), agriculture (13.5%), retail trade (13.7%), public administration (7.7%) and construction (6.3%). The majority of employed persons are private wage and salary workers (63%) with the remainder working for Federal, state or local government (26%) or self-employed (11%).

Study Area

The actual study area is comprised of approximately 25 acres along both sides of Main Street in the commercial district of Fort Fairfield. Main Street is located adjacent to the Aroostook River and its low-lying one-half mile stretch between Peterson's Garage and the Canadian Pacific Railroad Office has been the scene of many floods. Most of the flooding occurs during the springtime because of snowmelt and in many instances is exacerbated by ice jams.

The character of the study area is mostly commercial, however, there is a concentration of senior citizen housing units. There are 30 commercial structures in the area which house 41 separate commercial activities, 4 fraternal organizations and one government agency. Of these 30 structures, 5 have apartments on the second story and one has a total of 25 apartments on its second and third stories. There is only one traditional two-story, two-family house in the study area, but there are two senior citizen housing complexes. The first, Northern House, is a 3-story structure which contains 26 apartments. The second is the Fields Lane Senior Citizen Complex and is operated by the Housing Authority of Fort Fairfield. The complex is a campus type layout with 9 detached structures accounting for a total of 40 units plus a community center. Rounding out the structural inventory of the study area are two government buildings, one the U.S. Post Office and the other the Fort Fairfield Municipal Building which is occupied by town offices, the Police Department and Fire Department.

Valuation of Properties in the Study Area

In November 1986 the Town of Fort Fairfield provided the total value, based on Town Assessor's records, of the properties in the Main Street study area. The value of land is \$502,860 and buildings is \$3,641,000 for a total value of \$4,143,860. Town officials indicate that this figure is roughly 94 percent of current market value.

Flood Damage Surveys

Flood damage surveys are performed at the start of every Corps of Engineers flood control study in order to determine the need for improvements by estimating the magnitude of potential flood-related losses. These losses are estimated, at each flood-prone structure and site, starting at the elevation at which flooding and damage begins up to the elevation of floodwater associated with a very rare event such as the 500 year storm. Damages are estimated in one-foot increments between these two limits. The categories of these losses are: commercial, industrial, residential, agricultural and public. The two types of losses are physical and non-physical. Physical losses relate to grounds, site, structure, contents, utilities and clean-up. Non-physical losses are those additional induced costs which result from loss of use of a flooded structure. Residential non-physical losses are the costs of food, lodging and necessities while unable to use one's residence. For commercial and industrial firms non-physical losses are measures such as lost income and profit while shut down plus the cost of temporary quarters and services. In addition to the structure-related loss categories above, the flood damage survey estimation process also covers two general loss categories: (i) cost of emergency services and (ii) damages and costs to transportation, communication and utility systems.

The first flood damage survey of the Fort Fairfield study area was performed in October 1977 by a private consulting engineering firm as part

of the larger St. John River Basin study. In October 1982, damage evaluators from the New England Division performed a major on-site update. Updates have been performed recently in November 1985 and December 1986 to document improvements which have taken place in the study area.

Recent and Planned Improvements in Study Area

In 1985 the State of Maine awarded a Community Development Block Grant in the amount of \$820,000 to fund the 2-year Fort Fairfield Downtown Revitalization Project. Under this project certain commercial buildings were renovated and expanded and some older buildings were razed. Private investment in the study area was also made during 1986. The Irving Oil Co. constructed a large gas station, grocery store and liquor store. In 1987, the State of Maine, Department of Transportation plans to completely excavate and construct a new roadway and sidewalks for Main Street in the study area. Other improvements for Main Street scheduled for 1987 are: (i) the installation of 125 new street lights, (ii) installation of a new 8 inch sanitary sewer line (1600 linear feet) with manholes and service extensions and (iii) reinforcement of the existing telephone system, both underground and aerial, along Main Street by New England Telephone. The total cost for these 4 scheduled improvements is \$1,500,000.

Susceptibility to Flooding

One indicator of an area's susceptibility to damage from flooding is the relationship of the first floor elevation of structures in the floodplain to the elevation of floodwaters from certain events. First floor elevations were obtained for all floodplain structures by a field survey crew and potential flood elevations were obtained from an "elevation vs. frequency" curve produced by the Water Control Branch (Hydrologic Engineering Section) of the New England Division. The summary table below shows the relationship between flood elevation, frequency and number of structures affected. The salient point of the table is that even a storm of 10 year frequency will produce a flood level that will cover the first floor of 25 of the 43 floodplain structures.

TABLE 1
STRUCTURES SUSCEPTIBLE TO FIRST-FLOOR FLOODING
FORT FAIRFIELD STUDY AREA

| <u>Event</u> <u>(year)</u> | <u>Annual % Chance</u> <u>of Occurrence</u> | <u>Flood</u> <u>Elevation</u> (NGVD) | <u>Structures w/ First Floor Flooding</u> | |
|-------------------------------|--|--|---|-------------------|
| | | | <u>Number</u> | <u>% of Total</u> |
| 100 yr. | 1% | 367.3' | 37 | 86% |
| 50 yr. | 2% | 366.4' | 33 | 77% |
| 10 yr. | 10% | 363.9' | 25 | 58% |

Recurring Losses

Recurring losses are those potential flood related losses which are expected to occur at various stages of flooding under present day development conditions. Table 2 below displays the dollar value of potential flood-related losses, by damage category, that are estimated to occur if that specific flooding event were to occur today.

TABLE 2
RECURRING FLOOD LOSSES
FORT FAIRFIELD STUDY AREA

| Category | 10 Year Event (el. 363.9') | 50 Year Event (el. 366.4') | 100 Year Event (el. 367.3') | 500 Year Event (el. 369.2') |
|-----------------|----------------------------------|----------------------------------|-----------------------------------|-----------------------------------|
| Properties | \$1,107,000 | \$3,592,000 | \$4,678,000 | \$6,795,000 |
| Emergency Costs | 14,800 | 24,600 | 33,800 | 53,200 |
| Downtown Roads | 20,000 | 239,400 | 273,100 | 273,100 |
| Railroads | 87,300 | 174,500 | 174,500 | 174,500 |
| Total Losses | \$1,229,100 | \$4,030,500 | \$5,159,400 | \$7,295,800 |

Annual Losses

Recurring losses, discussed above, are informative inasmuch as they relate the dollar value of flood losses to specific depths of flooding, however they don't offer any information as to what the chances are of those flooding depths occurring in any given year. For the purpose of determining the severity of potential flooding the statistical concept of expected value is employed. For flood control studies the term used to measure the severity of potential flooding on an annual basis is "annual losses." Annual losses are calculated by integrating two sets of data: (i) recurring losses displayed in one-foot increments of flood depth from start of damage to the 500 year storm elevation and (ii) the estimated annual percent chance that flooding will reach each specific elevation for which recurring losses were estimated. Recurring losses are obtained by the flood damage survey process and the annual percent chance of occurrence for each event is obtained from a stage-frequency curve. This curve, estimated by the Hydrologic Engineering Section at NED, displays flood stages on the X-axis and the annual percent chance of reaching that stage on the Y-axis. Annual losses are computed for each event from the one that first causes damage to the 500 year event. Losses for all events are aggregated and this total estimate of expected annual losses represents the degree of flooding severity in the study area. The effectiveness of each alternative plan that is formulated for flood reduction is measured by the extent to which it reduces annual losses. Annual losses, by category, for the Fort Fairfield study area are displayed in Table 3.

TABLE 3
ANNUAL LOSSES
FORT FAIRFIELD STUDY AREA

| <u>Category</u> | <u>Annual Losses</u> |
|-----------------|----------------------|
| Properties | \$398,400 |
| Emergency Costs | 2,800 |
| Downtown Roads | 12,300 |
| Railroads | 47,000 |
| Total | \$460,500 |

Economic Benefit Analysis

Benefits from plans for reducing flood hazards accrue primarily through the reduction in actual or potential damages associated with land use. Benefits fall into three categories reflecting different responses to a flood hazard reduction plan. The inundation reduction benefit accrues when land use is the same with or without the plan and is defined as the increased net income generated by that use. The intensification benefit also accrues when land use is unchanged and is defined as the increase in net income based on a modification of the method of operation by floodplain occupants because of the plan. The location benefit accrues when an activity is added to the floodplain because of a plan and is measured as the difference between aggregate net incomes in the economically affected area with and without the plan.

Under the "with plan" condition for the Fort Fairfield study area, land use is projected to remain essentially the same. Since the area is the center of commercial activity and has a considerable number of permanent elderly housing units, it is projected that these functions will continue into the foreseeable future. This projection is nearly irrefutable based on the public and private investments in the area's infrastructure and commercial activities during 1985 to 1987. There probably will be modifications to existing activities and development on some of the few vacant lots, with the plan, but it is not expected to be on a large enough scale to significantly affect future losses and benefits. Therefore, benefits which accrue to the improvement plans will be measured under the category of inundation reduction only.

Inundation Reduction Benefit

The increase in net income that accrues under this category is measured by the decrease in the dollar value of outlays associated with reduced flood losses. The national economic development (NED) objective is satisfied if an improvement plan produces the beneficial impact of reducing annual losses.

Improvement Plans Evaluated

Three improvement plans, each offering a different level of protection, were evaluated. All three plans involve a 3000 foot long earthen dike which would extend from just upstream of Peterson's Repair Garage downstream to the Canadian Pacific Railroad Office. The plans to be evaluated offer flood protection against the following 3 events: (i) 500 year, (ii) 100 year and (iii) 50 year.

Benefit Estimation

Benefits for inundation reduction were calculated based on the flood elevation corresponding to each event. The top elevation of each dike plan is that flood elevation plus an additional 3 feet of freeboard to account for wave run-up and wind effects. Corps of Engineers regulations allow benefits to be taken up to the top of the dike plus 50 percent (1.5 feet) of the freeboard range. The benefits to each plan are the summation of annual losses prevented by the dike taken to an elevation 1.5 feet below the absolute top of dike including freeboard. The benefits for each plan are enumerated in Table 4.

TABLE 4
ANNUAL BENEFITS - INUNDATION REDUCTION
FORT FAIRFIELD STUDY AREA

| <u>Category</u> | <u>Annual Inundation Reduction Benefits</u> | | |
|-----------------|---|--------------------------------------|-------------------------------------|
| | <u>Level of Protection</u> | | |
| | <u>500 Year</u> <u>(el. 369.5')</u> | <u>100 Year</u> <u>(el. 368')</u> | <u>50 Year</u> <u>(el. 367')</u> |
| Properties | \$387,400 | \$362,200 | \$327,000 |
| Emergency Costs | 2,800 | 2,600 | 2,300 |
| Downtown Roads | 11,900 | 10,700 | 8,900 |
| Railroads | 46,600 | 46,000 | 44,800 |
| Total | \$448,700 | \$421,500 | \$383,700 |

Reduced Pumping Costs

A second type of flood related cost that will be reduced by the dike plan is the increased pumping costs at the Fort Fairfield Sewage Treatment Plant during times of flooding. There is a sewer pipe which runs along the entire length of the site where the dike would be constructed. This pipe would require relocation closer to Main Street, away from the river bank if the dike were to be constructed. In order to determine if economic benefits would accrue to this relocation, the manager of the Fort Fairfield Utilities District was interviewed. The pipe does not currently sustain direct damage from flooding or erosion. It was installed in 1976, is made of PVC, is buried 13 to 17 feet below ground and has an expected life of 60 years. However, during periods of flooding at the pipe's

location, especially in springtime, inflow and infiltration of floodwaters into the pipe occurs at manholes and around some pipe joints. Pumping at the treatment plant increases dramatically from an average of 0.4 MGD to 1.5 MGD during times when floodwaters enter the system and continues at the elevated rate for 2 weeks after flooding subsides. There are two negative effects caused by this inflow. First, the pumping system is overburdened and must pump flood water that doesn't need treatment. Because of this, untreated sewage also gets pumped into the river. The Utilities District is currently under a consent decree from the Maine Department of Environmental Protection to control the inflow. Secondly, the increased volume which needs to be pumped during times of flooding increases the pumping costs. Under the with-plan condition, the section of pipe where inflow and infiltration occurs will be relocated to the inside of the dike, closer to Main Street and further away from the river-bank. The manager of the Utilities District indicates that this relocation of the pipe should solve the inflow/infiltration problem as the manholes will be in the flood protection area. The pumping plant will not be overburdened, pumping costs will remain at normal levels, and untreated sewage will not be pumped into the river, thereby keeping the Utility District in compliance with its State and Federal licenses. The benefit to be realized with the project is estimated to be \$2,000 annually in reduced pumping and associated repair costs.

Reduction in Flood Insurance Overhead Costs

A cost of floodplain occupancy is flood insurance overhead costs. This administrative cost is national in nature and will be eliminated with the 500 year and 100 year dike improvement plans. The 1986 overhead cost per policy is \$67 and an estimated 36 policies are in effect in the study area. With the improvement plan the annual benefit is \$2,400.

Summary of Benefits

The annual benefits expected to accrue under each of the 3 flood protection plans are exhibited in Table 5 below.

TABLE 5
SUMMARY OF ECONOMIC BENEFITS
FORT FAIRFIELD FLOOD REDUCTION PLANS

| <u>Category</u> | <u>500 Year Protection</u> | <u>Annual Benefits 100 Year Protection</u> | <u>50 Year Protection</u> |
|---|--------------------------------|--|-------------------------------|
| Inundation Reduction: | | | |
| Properties | \$387,400 | \$362,200 | \$327,700 |
| Emergency Costs | 2,800 | 2,600 | 2,300 |
| Downtown Roads | 11,900 | 10,700 | 8,900 |
| Railroads | 46,600 | 46,000 | 44,800 |
| Reduced Pumping Costs (Sewage Treatment Plant) | 2,000 | 2,000 | 2,000 |
| Reduction in Flood Insurance Overhead Costs | 2,400 | 2,400 | - |
| TOTAL BENEFITS | \$453,100 | \$425,900 | \$385,700 |

Economic Justification

The ultimate purpose of the economic analysis is to compare the benefits estimated for each plan to the annual costs of plan implementation in order to determine the benefit-cost ratio which is the measure of economic justification and indicator of Federal participation.

TABLE 6
ECONOMIC EVALUATION OF PLANS

| | <u>500 Year Protection</u> | <u>100 Year Protection</u> | <u>50 Year Protection</u> |
|-----------------------|--------------------------------|--------------------------------|-------------------------------|
| Total Annual Benefits | \$453,100 | \$425,900 | \$385,700 |
| Total Annual Costs | \$435,000 | \$385,000 | \$361,000 |
| Benefit-Cost Ratio | 1.04 | 1.11 | 1.07 |
| Net Benefits | \$18,100 | \$41,900 | \$24,700 |

SECTION E


REAL ESTATE

DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
424 TRAPELO ROAD
WALTHAM, MASSACHUSETTS 02154-9149

PRELIMINARY ESTIMATE OF REAL ESTATE COSTS
FORT FAIRFIELD LOCAL PROTECTION PROJECT
AROOSTOOK RIVER, FORT FAIRFIELD, MAINE


May 1987

PREPARED BY:



ROBERT P. ABBOTT
Staff Appraiser

REVIEWED &
APPROVED BY:



WILLIAM D. BROWN, JR.
Chief, Appraisal Branch

TABLE OF CONTENTS

| ITEMS | PAGE |
|--|-------|
| PURPOSE | 1 |
| INSPECTION OF THE REAL ESTATE | 1 |
| LOCATION & AREA DATA | 1 |
| HISTORY | 1 |
| PROJECT DESCRIPTION | 2 |
| TAX LOSS | 2 |
| ACQUISITION COSTS | 2 |
| RELOCATION COSTS | 3 |
| SEVERANCE DAMAGE | 3 |
| PROTECTION AND ENHANCEMENT OF CULTURAL ENVIRONMENT | 4 |
| ZONING | 4 |
| HIGHEST AND BEST USE | 4 |
| MINERAL DEPOSIT | 4 |
| CROPS | 4 |
| UTILITIES & SERVICES | 4 |
| WATER RIGHTS | 4 & 5 |
| BORROW AREA | 5 |
| RELOCATIONS - ROADS AND PUBLIC UTILITIES | 5 |
| CONTINGENCIES | 5 |
| GOVERNMENT-OWNED FACILITIES | 5 |
| RIGHTS TO BE ACQUIRED | 5 |
| FEE REQUIREMENTS | 5 & 6 |
| BASEMENT AREAS (PERMANENT & TEMPORARY & EXISTING) | 6 & 7 |
| EVALUATION AND CONCLUSION | 7 & 8 |
| GROSS APPRAISAL | 8 |
| COST SUMMARY | 9 |
| ADDENDA | 10 |
| COMPARABLE SALES CHARTS | 11 |
| COMPARABLE MAP | 12 |

1. PURPOSE

The purpose of this report is to estimate the preliminary real estate cost associated with the Fort Fairfield Flood Control Project located in Fort Fairfield, Aroostook County, Maine.

2. INSPECTION OF THE REAL ESTATE

The properties affected by the proposed project were inspected/viewed in the field in May, 1987, by Staff Appraiser Robert P. Abbott, of New England Division, Corps of Engineers.

3. LOCATION AND AREA DATA

Fort Fairfield is located near the Canadian Border in northeastern Maine on the southern bank of the Aroostook River. The Great Atlantic & Pacific Tea Co. operates a \$3.6 million dollar potato and pea processing plant in Fort Fairfield that employs approximately 200 people.

The area is serviced by U.S. Highway 1A and State Highway 167 in addition to two railroads, the Canadian Pacific and the Bangor & Aroostook. At present, Fort Fairfield is a progressive agricultural community.

4. HISTORY

Floods along the Aroostook River have occurred to varying degrees over the years resulting from intense rainfall, snowmelt and ice jams or from combinations of the three. The main flood season on the Aroostook River occurs in the spring when heavy rain accompanied by snowmelt combined to cause considerable runoff; fall season floods which can occur from rains accompanying coastal hurricanes and tropical storms are generally lower in magnitude than spring floods. Ice jams in the Aroostook River cause a major flood hazards most every spring. Most notable past historic floods are the April 1973 and April 1983 events.

The recent April 3, 1986 ice-out flood stage caused road inundation and flooding of commercial property along Main Street with as much as 3 feet of water at one property.

According to local officials and historical records, a recurring April 1973 event in the project study area would cause an estimated \$500,000 in average annual damages to commercial and residential property, the adjacent railroad, and to downtown streets in Fort Fairfield. The April 1973 event had an estimated discharge of 58,200 cfs at Fort Fairfield.

5. PROJECT DESCRIPTION

The selected plan for local flood protection in Fort Fairfield consists of an earth dike approximately 2,900 feet long with stoplog railroad gates at each end, a 65 cfs capacity pumping station for low level interior drainage behind the dike, and a 4-foot diameter pressure conduit for high level drainage. The dike extends from just downstream of Limestone Road bridge at top elevation 370.5 feet NGVD and continues easterly along the riverbank, extending to high ground at a point just upstream of the railroad station in downtown Fort Fairfield at top elevation 369.0 feet NGVD. The dike should provide flood protection to commercial and residential properties on the north side of Main Street. (See Plate 7)

The top of dike will vary approximately 15-20 feet above existing ground with a top width of 12 feet. The dike core will be compacted impervious fill. The riverside and landside slopes will be 1 vertical to 2.5 horizontal. The riverside slope will have a dumped gravel toe berm. Stone protection (1.5 feet thick) will be placed on the toe and a 1-foot gravel bedding layer underlain by the compacted impervious fill above the toe berm. Stone sizes will be approximately 1-foot in diameter except at the transition sections where it will be approximately 2 feet in diameter. The landslide slope will be protected by 6 inches seeded topsoil and a gravel toe trench.

6. TAX LOSS

The anticipated tax loss for the Fort Fairfield Local Protection Project, based upon the 1986 tax assessments of the town is estimated to be approximately \$1,900.00 dollars, which was furnished by local town officials.

7. ACQUISITION COSTS

Acquisition costs will include costs mapping and surveys, legal description, title evidence, appraisals, negotiations, and closing and administrative costs for possible condemnations. The acquisition costs are based upon this office's experience in similar civil works projects in this general area and are estimated at \$3,000 per ownership.

19 OWNERSHIPS x \$3,000.00 = \$57,000.00

8. RELOCATION COSTS

Public Law 91-646, Uniform Relocations Assistance Act of 1970, provided for equitable treatment of persons displaced from their homes, businesses, or farms by a Federally Assisted Program. In accordance with this law, a sum of \$200 per ownership is estimated to cover possible reimbursable expenses incidental to transfer of real estate interests which may be incurred by the ownerships in this acquisition program.

Included among the items under P1 91-646 are the following:

- a. Moving Expenses
- b. Relocation allowance (Business)
- c. Replacement Housing (Tenants)
- d. Relocation Advisory Services
- e. Recording Fees
- f. Transfer Taxes
- g. Mortgage Prepayment Costs
- h. Real Estate Tax Refunds (Pro-Rata)

Preliminary surveys indicate that no relocation of existing residential and commercial properties will be required for the proposal project.

ESTIMATE OF THE RELOCATION COSTS

19 OWNERSHIPS X \$200.00 EACH = \$3,800.00

9. SEVERANCE DAMAGES

Severance damages usually occur when partial takings are acquired which restrict the remaining portion from full economic development. The severance damages are measured and estimated on the basis of a "Before" and "After" appraisal method and will reflect actual value loss incurred to the ownerships as a result of partial acquisition.

Preliminary investigation indicate that no ownership will incur severance damage because of the taking. The acquisition will be under Permanent Easements.

ESTIMATE OF SEVERANCE DAMAGES = -0-

10. PROTECTION AND ENHANCEMENT OF CULTURAL ENVIRONMENT

In accordance with instructions set forth in Teletype DA (DAEN) R 111306A, dated October 1971, Subject: "EO11593, 13 May 1971, Protection and Enhancement of Cultural Environment; and DA AR200-1 dated 15 July 1982; "our preliminary field investigations revealed that no local, State, Federally owned nor Federally controlled property of historical significance would fall within the provisions of EO11593 and AR200-1.

11. ZONING

The lands affected by the project are zoned commercial.

12. HIGHEST AND BEST USE

The highest and best use of the affected lands is considered to be the present use.

13. MINERAL DEPOSITS

A recent field inspection discloses no evidence of commercial mining or gravel nor the deposits of any minerals within the project area.

14. CROPS

Several trees have been killed off either by flood damage or disease. However, the quality and quantity of the healthy growth are considered inadequate to require inclusion of any special allowance for merchantable timber.

Agriculture - There is no evidence of any commercial agricultural efforts in the project area.

15. UTILITIES AND SERVICES

Electric power, telephone, Town water, and sanitary sewers are available to all properties within the project area.

16. WATER RIGHTS

Suggested interim guide lines for shore land zoning and subdivision control have been distributed to municipalities in Maine, and Department of Environmental Protection, State Planning Office. The guide lines are intended to assist communities with municipal shore land zoning.

All buildings and structures except those requiring direct access to the water as an operational necessity shall be set back at least 100 feet from the mean annual high water line.

Those standards may be waived by a municipality because of existing structures, and those requiring direct access to the water as an operational necessity. A recent inspection and discussion with the Town Manager revealed no ownerships in the project area require access to the River for their operational needs.

17. BORROW AREA

No land has been included in this report for borrow purposes.

18. RELOCATIONS - Roads and Public Utilities

No roads but public utilities (sewage) will require relocation. The main sanitary sewer which services this area of Fort Fairfield will be relocated in proposed Permanent Easement Area of this project.

19. CONTINGENCIES

A contingency allowance of 25 percent is considered to be reasonably adequate to provide for possible appreciation of property values from the time of this estimate to acquisition date, for possible minor property line adjustment or for additional hidden ownerships which may be developed by refinement of taking lines, for adverse condemnation awards and to allow for practical and realistic negotiations.

20. GOVERNMENT-OWNED FACILITIES

Section III of the Act of Congress approved 8 July 1958 (PL85-500) authorized the protection, realteration, reconstruction, relocation or replacement of Government-owned facilities. A preliminary inspection of the property area indicated no Government-owned facilities are affected.

21. RIGHTS TO BE ACQUIRED

Local interests are required to provide all lands, easements and rights-of-way necessary for project construction. Appraisals for acquisition will be received by this office.

22. FEE REQUIREMENTS

Preliminary investigations indicate that both improved and unimproved properties will be affected by the proposed Fort Fairfield Local Flood Control Project. Based on Project Engineering Plans, one fee acquisition will be required of the project. Lot 29 consisting of .37± acres of land (16,117 SF) owned by Pineland Development Corporation will be acquired in fee.

Therefore, the fee acquisitions that are necessary for the subject project are estimated as follows:

EEE ACQUISITIONS

| | | |
|--|---|-------------|
| LAND .37± acres (16,117 SF x \$.60 PSF) | = | \$ 9,670.20 |
| Call | | \$ 9,700.00 |

23. EASEMENT AREAS

A. Permanent Easement Areas

Permanent easements for construction and maintenance purposes are necessary. The easement areas adjacent to the waterway vary in width throughout the project area and contain approximately 4.06± acres.

Preliminary investigations indicate that after the imposition of the permanent easement interests adjacent to the waterway, their highest and best use of the remainder of the properties will not be materially affected. However, lands would remain in their private ownerships to maintain conformity with their existing lot requirements.

The following costs for the permanent easement interests are considered fair and reasonable for imposition of the 4.06± acre easement areas.

| | | |
|---------------------------------|---|--------------|
| 4.06± acres @ \$29,000 per acre | = | \$116,870.00 |
|---------------------------------|---|--------------|

B. Temporary Easement Areas

Construction measures would require temporary easements for contractor work areas along the entire length of the dike. The required work areas will be about 35 feet wide and will run contiguous to the inboard toe of the proposed dike length of 2,900 feet. Exceptions to their contiguity are at certain points where their close proximity to existing structure. In these cases, the structures will not be affected. The easements would affect about 16 private ownerships, and tow municipally owned parcels.

It is estimated that about 2.33 acres will be required for right-of-way and temporary construction easements. Right-of-ways to the proposed dike and pumping station will be situated on town-owned land which are included in the proposed project. The cost for temporary construction easements is estimated to be about 10 percent (10%) of the estimated market value of the land per year. This amount is predicated on an amount equal to the estimated fair return an investor would be entitled to on invested capital and

provision for economic tax. For purposes of this report, it is estimated that the temporary construction easements will be required for one year.

| | |
|--|-------------|
| 2.33± acres @ \$29,000 per acre | \$67,570.00 |
| Fair rate of return at 10% per year (for one-year) | _____x 10% |
| | \$ 6,757.00 |

24. EXISTING FLOWAGE EASEMENTS

The Maine and New Brunswick Electrical Power Company Limited constructed a dam about 1908, known as Tinker Dam, downstream from Fort Fairfield on the Aroostook River in New Brunswick, Canada.

Since the dam was constructed, there have been 70 or more flood damage claims filled with the power company alleging the damage was due to the fact that the dam caused the flooding. According to records of the power company, when these claims were settled they attempted to secure flowage easements over these properties. At least in some cases they were able to secure a flowage easement which reads in part:

"The right in perpetuity to flow from time to time as the needs of the Grantee, its successors and assigns may require to such heights as they may be flowed by the maintenance of the Grantee's existing dam at Tinker in the said Province of New Brunswick at its present elevation with flashboards at the level of 498 as established by a brass plug in the cutoff wall of the head works of said dam, the Grantors' premises situated in said Fort Fairfield bounded and described as..."

Pending a detailed title examination of each ownership involved, it would be difficult to identify which ownerships have flowage easements to the extent thereof.

25. EVALUATION AND CONCLUSION

A thorough search of the records was made in the Town of Fort Fairfield, Maine to obtain comparable sales data. In addition real estate brokers, local officials, and knowledgeable persons were interviewed to obtain data and value estimates. This evaluation is based upon the knowledge of the general real estate market in the area which was obtained from this study and analysis. All of the properties affected within the project area have been inspected from the exterior. A random sample of interiors were also inspected when owners were interviewed.

The trend of property values in the Town of Fort Fairfield appear to be static as evidenced by the few new construction starts and limited real estate transfers. For the most part, business properties and commercial establishments that are affected by the proposed project purchase area have remained in the same family ownerships for many years.

The assigned values used in this estimate are for the most part considered nominal which reflect both small and large tracts of land with differing characteristics. Based on this fact real estate market values are estimated at \$29,000.00 per acre, with a square foot market value of \$.60 PSF, due to its characteristics.

26. GROSS APPRAISAL

The following is a summary of the real estate required; its estimated market value:

EEE

IMPROVEMENTS

None

-0-

LAND

| | | |
|------------------|---|-------------|
| 0.37± Acre | Commercial Land (16,117 SF @ \$.60 PSF) | \$ 9,670.20 |
| Total 0.37± Acre | Cost Land & Improvements (Fee) | 9,670.20 |
| | Call | \$ 9,700.00 |

PERMANENT EASEMENT

| | | |
|-------------------|--|--------------|
| 4.06± Acres | Commercial Land @ \$29,000 per acre | \$116,870.00 |
| Total 4.06± Acres | Cost Land (Permanent Easement) | 116,870.00 |

TEMPORARY EASEMENT

| | | |
|--|--------------------------------|--------------|
| 2.33± acres | @ \$29,000 per acre | \$ 67,570.00 |
| Fair rate of return at 10% per year (for one-year)_____x_10% | | |
| Total 2.33± Acres | Cost Land (Temporary Easement) | \$ 6,757.00 |

COSTI SUMMARY

The following is a summary of the total estimated real estate costs of the proposed project:

| | |
|--|--------------|
| Total Cost 13.18 Acres Land & Improvements (Fee, Permanent & Temporary Easements) | \$133,327.00 |
| Severance Damages | -0- |
| Relocation Assistance | \$ 3,800.00 |
| Acquisition Costs | \$ 57,000.00 |
| Contingency Allowance (25%) | \$ 33,163.00 |
| TOTAL ESTIMATED REAL ESTATE COSTS | \$227,290.00 |
| ROUNDED TO | \$227,000.00 |

COMPARABLE SALES - FORT FAIRFIELD & ARQOSTOOK COUNTY, MAINE

| SALES NUMBER | DATE OF SALE | LOCATION | GRANTOR | GRANTEE | LAND AREA | ZONING | PRICE |
|-----------------|-----------------|-------------------|------------------------|-------------|--------------|--------|-------------|
| 1 | Dec. 1986 | Ft. Fairfield, ME | W. Adams | K. Thibeau | 1.43± | Comm. | \$29,800.00 |
| 2 | Aug. 1985 | Caribou, ME | M. Carter | R. Deschene | 1.0± | Comm. | \$37,000.00 |
| 3 | Aug. 1986 | Ft. Fairfield, ME | Dupree Realty Trust | D. Wilcox | 1.0± | Comm. | \$29,000.00 |
| 4 | Apr. 1986 | Presque Isle, ME | L. Roberts | C. Walton | 1.06± | Comm. | \$25,000.00 |